

Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in To3 to Chainpur For year 2020.

Head - 2245 Length- .850KM

SI No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Earth work in Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting Only and as per Technical Specification Clause 302.3	cum	As Per			Appendix I	587.500	442.47 482.42	242325.60 224671.80
2		Providing & Laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum	As Per			Appendix II	150.94	2085.03	314709.22 314714.40
3		Providing and laying reinforced cement concrete pipe NP3 for Cross Drainage 1000mm dia	RM	1Row x2Nos x2.50M=			5M	0.000	4032.75	0.00
TOTAL (in Rs.)										557034.82

Say Rs ~~557000.00~~ 539386.20
5,39,000.00

H/S
21/12/20
Junior Engineer,
Rural Works Department,
Works Section, Raxaul

drd
21/12
Assistant Engineer,
Rural Works Department,
Works Sub Division, Raxaul

drd
21/12/2020
Executive Engineer,
Rural Works Department,
Works Division, Raxaul

Post Facto T.A./TS is accorded for Rs. 5,39,000.00
(.....crore.....Five.....lacs.....Thirty Nine.....
.....hundred.....) Only

drd
29.12.20
S.E. (R.W.D.)
works Circ.
Motihari