

Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in T01 PWD Road to Manguraha (BR-11R-474) For year 2020.

Head - 2245 Length-1.7KM

Sl No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Earth work in Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting Only and as per Technical Specification Clause 302.3	cum	As Per			Appendix I	694.840	412.47 382.42	286600.07 265721.10
2		Providing & Laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum	As Per			Appendix II	63.788	2116.22	134988.38
3		Providing and laying reinforced cement concrete pipe NP3 for Cross Drainage 1000mm dia	RM	1Row x2Nos x2.50M=			5M	5.000	4032.75	20163.76
TOTAL (in Rs.)									441752.22	

Say Rs 442000.00

4,21,000

[Signature]
21/8/20

Junior Engineer,
Rural Works Department,
Works Section, Adapur

[Signature]
21/8/20

Assistant Engineer,
Rural Works Department,
Works Sub Division, Adapur

[Signature]
21/8/20

Executive Engineer,
Rural Works Department,
Works Division, Raxaul

Net fact T.A./TS is accorded for Rs. 4,21,000.00
(.....crore.....lacs.....
.....hundred.....

[Signature]
29/12/20
S.E. (R.W.D.)
works Circle
Motihari