


Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in Nh-28A Path Chiljhapti To Sah Tola Katkenwa For year 2020.


Head - FDR Length-2.30KM

SI No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Labour for laying dry graded Jhama Khoa or stone filter under Brick Pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/L.	cum	As Per	Appendix I			328.509	2116.22	695196.79
2		Providing and laying reinforced cement concrete pipe NP3 for Cross Drainage 1000mm dia	RM	1Row x2Nos x2.50M= 5M				5.000	4032.75	20163.76
TOTAL (in Re.)										715360.55


Say Rs 715000.00

  
Junior Engineer,  
Rural Works Department,  
Works Section, Ramgarhwa

  
Assistant Engineer,  
Rural Works Department,  
Works Sub Division, Ramgarhwa

  
Executive Engineer,  
Rural Works Department,  
Works Division, Raxaul

Post factor A.T.S is accorded for Rs. 7,15,000.00  
(Seven lacs, fifteen thousand  
hundred only.)

  
S.E. (R.W.D.)  
Works  
Motilal  
29.12.20