



GOVERNMENT OF BIHAR

NAME OF WORK- Restoration work of road & Culvert in road Akilpur REO road to Karamchak

(FDR PART-A)

Length-4.5km

BLOCK-DARIYAPUR

DETAILED PROJECT REPORT UNDER FDR(2245)

ESTIMATED COST

Rs-4.939 Lacs

..PREPARED BY :-
EXECUTIVE ENGINEER
RWD(W) DIVISION
SONPUR

Inspection Report for flood damage work

Date:

1. Name of PIUs- R.W.D.C.W. Div Sonpur

2. Name of Block/Road- Daryapur, Akiapur R.G.O road to Karamchak road

A. For Road

1. Damage Location/Chainage CH-500m-800m, CH-900m-1000m

2. Damage Length : 392 m

3. Nature of Damage : Earthen road washed

4. Details of Restoration :

i Material being used in Restoration : No

ii Equipment/Tools being used in Restoration works: Yes

iii Procedure taken up in Restoration works

iv Restored Length — 392 m

Filling with C.W. and
Compacting with road roller

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration :


ii Equipment/Tools being used in Restoration works:


iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE


10/12/20


10/12/20
AE


13/12/2020

Signature

(Name of Inspector)

प्रमंडल का नाम:

ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर

कार्य का नाम:-

सारण जिला अन्तर्गत दरियापुर प्रखंड में अकिलपुर REO रोड से करमचक पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्ण:स्थापन कार्य।

पथ की कुल लम्बाई:- 4.50कि०मी०

क्षतिग्रस्त पथ की लम्बाई:- ~~400~~³⁹²मी०


प्राक्कलित राशि:-4.939 लाख


प्रतिवेदन


यह प्राक्कलन सारण जिला अन्तर्गत दरियापुर प्रखंड में अकिलपुर REO रोड से करमचक पथ का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्ण:स्थापन कार्य का प्राक्कलन का तैयार किया गया है। इस वर्ष अत्यधिक बाढ़ आने के कारण Ch-500M से Ch-800m एवं CH-900 से CH-1000मी० पथांश पानी में कई दिनों तक डूबे रहने के कारण पथ बिल्कुल क्षतिग्रस्त हो गया है, जिसके कारण पथ से आवागमन दुष्कर हो गया है।

प्रस्तावित प्राक्कलन में पथ के कटे हुए पथांश में मिट्टी से भरकर पुर्नस्थापित किया गया है।

यह प्राक्कलन वर्तमान अनुसूचित दर पर तैयार किया गया है, जिसकी स्वीकृति आपेक्षित है।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा दरियापुर



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल दरियापुर



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, सोनपुर

Restoration work of road & Culvert in road Akilpur REO road to Karamchak


Length of road-	
ABSTRACT OF COST	
1 Cpost of Emergent repair of road & Bridge	Rs. 437,122.44
2 Add 1% Labour Cess	Rs. 4,371.22
3 Add 12% GST	Rs. 52,454.69
Total	Rs. 493,948.35
Say	Rs. 493,900.00


Junior Engineer
RWD(W) Dariyapur


10.12.20
Assistant Engineer
RWD(W) sub division Dariyapur


13/12/2020
Executive Engineer
RWD(W) DiV
Sonpur

T/A Approved for Rs. 4.939 Lakh (Rupees Four lacs ninety three Thousand nine hundred) only


S.E. Chafory

Restoration work of road & Culvert in road Akilpur REO road to Karamchak

o 1	Item of work	Nos	Length	width	Height	Quantity	unit	Rate	Amount
	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5								
	CH-500M to CH-800M	1	310	6.0	(0.00+1.82) 2	1692.60			
	CH-900M to CH-1000M	1	82	3.3	(0.00+1.52) 2	202.54			
						1895.14	cum	230.65	437122.44
									Rs. 437,122.44

[Signature]
10/12/20
Junior Engineer
RWD(W) Dariyapur

[Signature]
10.12.20
Assistant Engineer
RWD(W) sub division
Dariyapur

[Signature]
10/12/20
Executive Engineer
RWD(W) Div Sonpur