

Name of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in Saunaha chowk to Nahar Tola For year 2020.

Head - 2245 Length- 1.10KM

SI No.	Item No.	Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Earth work in Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting Only and as per Technical Specification Clause 302.3	cum	As Per			Appendix I	131.250	412.47 332.42	54136.57 50192.63
2		Providing & Laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum	As Per			Appendix II	105.00	2085.03	218928.15
3		Providing and laying reinforced cement concrete pipe NP3 for Cross Drainage 1000mm dia	RM	1Row x2Nos x2.50M=			5M	0.000	4032.75	0.00
TOTAL (in Rs.)										273064.72

Say Rs ~~273000.00~~
2,69,000.00 2,69,120.280

[Signature]
21/12/20
Junior Engineer,
Rural Works Department,
Works Section, Raxaul

[Signature]
21/12/20
Assistant Engineer,
Rural Works Department,
Works Sub Division, Raxaul

[Signature]
21/12/20
Executive Engineer,
Rural Works Department,
Works Division, Raxaul

Post Facts T.A./TS is accorded for Rs. 2,69,000.00 = 2
(.....crore.....Two lacs Sixty Nine thousand
.....hundred.....) only.

[Signature]
29.12.20
S.E. (R.W.D.)
works Circle
Motihari