

34 29 To

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs : Gopalganj - 2

2 Name of Block/Road : Baikunthpur / PMGSY Road To Banhi Tola

A For Road

1 Damage Location / Chainage : 100m to 300 m

2 Damage Length : 120 m

3 Nature of Damage : Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works : Brick Bats

ii Equipments / Tools being used in Restoration Works : JCB, Grader, Tractor, Blower, Shovel, Roller

iii Procedure taken up in Restoration Works : Yes

iv Restored Length : 120 m

B For Bridge

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

25/9/2020
JE

25/9/2020
AE

25/9/2020
EE

25/9/2020
Signature
Executive Engineer
(Name of Inspector)
R.W.D. W.D.
Hathua



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

PMGSY Road To Bandh Tola

ESTIMATED COST - RS. 494500.00

**SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2**

Report

Name of Work :- Motorable work of PMGSY Road To Bandh Tola


Estimated Cost :- 494500.00

Total length of Road :- 0.595 km

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road. Hence there has been a provision of laying R.C.C. NP3 1000MM Dia hume pipe.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


19/9/2020
J.E.


19.09.2020
A.E.


19/9/20
E.E.

ailed Estimate For Motorable Work in Road from PMGSY Road To Bandh Tola damaged due to Heavy rain/flood for year 2020-2021

	Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
1	Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
	CH - 100 M to 300 M	1	6.00	6.00	1.10	39.60	M3		
		1	8.00	1.20	0.60	5.76	M3		
		1	12.00	1.60	1.10	21.12	M3		
		1	15.00	3.50	1.20	63.00	M3		
		1	10.00	2.00	1.20	24.00	M3		
		1	24.00	1.80	1.30	56.16	M3		
		1	30.00	1.80	1.20	64.80	M3		
		1	15.00	1.40	0.84	17.64	M3		
	Less for H.P.	1.58	1.23	1.23	5.00	11.95	M3	2412.11	465851.20
						193.13		2427.65	468847.41
2	Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	2	2.50			5.00	M	2744.50 4159.56	13723.20 20797.80
									479574.20
									489645.21
									4776.50
	Add 1 % Contingency								4896.45
									484376.21
								Total	494541.66
								Say	494500.00

484376.20
Say Rs 4.8436

[Signature]
19/9/2020
J.E.

[Signature]
13.09.2020
A.E.

[Signature]
19/9/20
E.E.

Technically Approved For Rs 4.8436 (Rupees Four Lac Eighty Four Thousand Thousand & Three Hundred) only

[Signature]
21/01/21

Superintending Engineer
RWD Works Circle, Siwan