

52

(2A)

Inspection Report For Flood Damage Work

Date:

1 Name of PIUs: Gopalganj - 2

2 Name of Block/Road: Baikunthapur / Saran Bandh PMSY TO Chakeri Gaon.

**A For Road**

1 Damage Location / Chainage: 600m to 1100 m

2 Damage Length: 394m

3 Nature of Damage: Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Ball

ii Equipments / Tools being used in Restoration Works: JCB, Tractor, Trolly, Belcher, Shovel

iii Procedure taken up in Restoration Works: Yes

iv Restored Length: 394m

**B For Bridge**

N/A.

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works:

ii Equipments / Tools being used in Restoration Works:

iii Procedure taken up in Restoration Works:

iv Restored Length:

*[Signature]*  
25/9/2020  
JE

*[Signature]*  
25.09.2020  
AE

*[Signature]*  
28/9/2020  
EE  
Signature  
(Name of Inspector)



# ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

## FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR  
DISTRICT :- GOPALGANJ  
BLOCK :- BAIKUNTHPUR

Saran Bandh PMGSY Sadak To Chakri Gaon

ESTIMATED COST - RS.

~~1945900.00~~ Rs 19,27500.00

SUBMITTED BY :-  
EXECUTIVE ENGINEER  
RWD (W) DIVISION  
GOPALGANJ-2

## Report

**Name of Work** :- Motorable work of Saran Bandh PMGSY Sadak To Chakri Gaon

**Estimated Cost** :- ~~1945900.00~~ Rs 1927500.00


**Total length of Road** :- 1.85 km

**Description** :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.

  
19/9/2020  
J.E.

  
19-09-2020  
A.E.

  
19/9/20  
E.E.



# alied Estimate For Motorable Work in Road from Saran Bandh PMGSY Sadak To Chakri Gaon damaged due to Heavy rain/flood for year 2020-2021

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in litches including all cost of labour & material with all complete job.								
CH - 600 M to 1100 M	1	30.00	5.00	0.60	90.00	M3		
	1	29.00	6.00	0.55	95.70	M3		
	1	15.00	5.00	0.50	37.50	M3		
	1	26.00	3.50	1.00	91.00	M3		
	1	30.00	2.40	1.00	72.00	M3		
	1	24.00	2.50	0.35	21.00	M3		
	1	30.00	2.30	1.10	75.90	M3		
	1	30.00	1.20	1.20	43.20	M3		
	1	26.00	4.20	0.45	49.14	M3		
	1	24.00	2.30	0.80	44.16	M3		
	1	26.00	2.40	0.50	31.20	M3		
	1	30.00	1.30	0.65	25.35	M3		
	1	26.00	1.20	0.60	18.72	M3		
	1	<del>30.00</del>	5.00	0.50	<del>75.00</del>	M3		
	1	18.00	2.20	0.60	23.76	M3		
							2412.11	1896232
					-793.63	M3	2427.65	1926655.87
Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			786.13	M	2733.85	1908448.49
					0.00	M	4159.56	0.00
								1908448.49
								1926655.87
								1908448.49
Add 1 % Contingency							189622	19266.56
								1908448.49
							Total	1945922.43
							Say	1945900.00

Rs 1927500.00

Rs 1915194.20

Says Rs 19.152 Lacs.

*Pld*  
19/12/20

J.E.

*Signature*  
19.03.2020

A.E.

*Signature*  
19/12/20

E.E.

Technically Approved for Rs 19.152 Lacs (Rupees Nineteen Lacs Fifteen Thousand & Two Hundred only)

Superintending Engineer

B. H. P. Circle-Saran

*Signature*  
11/11/2021