

77

(49)

Inspection Report For Flood Damage Work

Date:

1 Name of PUs: Gopalgarh - 2

2 Name of Block/Road: Baikunthpur / Dharambari PWD Path To Kazi Nigra Ka
Ghar Tak

A For Road

1 Damage Location / Chainage: 300 m to 485 m

2 Damage Length: 151 m

3 Nature of Damage: Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Balls

ii Equipments / Tools being used in Restoration Works: JCB, Tractor, Pallet, Bullock, Shovel

iii Procedure taken up in Restoration Works: Yes 3 Roller

iv Restored Length: 151 m

B For Bridge

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works:

ii Equipments / Tools being used in Restoration Works:


iii Procedure taken up in Restoration Works:

iv Restored Length:


 AE

AE

EE


 Executive Engineer
 (Na. R. & W. D. Hathua)
 Hathua



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

Dharambari PWD Path To Kasi Miya Ke Ghar Tak

ESTIMATED COST - RS. 1036500.00

SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2

Report

Name of Work :- **Motorable work of Dharambari PWD Path To Kasi Miya Ke Ghar Tak**

Estimated Cost :- **1036500.00**


Total length of Road :- **0.435 km**

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.


19/9/20
J.E.


19.09.2020
A.E.


19/9/20
E.E.

Detailed Estimate For Motorable Work in Road from Dharambari PWD Path To Kasi Miya Ke Ghar Tak damaged due to Heavy rain/flood for year 2020-2021

| Sr. | Items | No. | L (M.) | W (M.) | D (M.) | Qty. | Unit | Rate | Amount |
|-----|---|-----|--------|--------|--------|--------|------|--------------------|------------|
| 1 | Providing brick bats billed in ditches including all cost of labour & material with all complete job. | | | | | | | | |
| | CH - 300 M to 435 M | 1 | 16.00 | 5.00 | 1.50 | 120.00 | M3 | | |
| | | 1 | 12.00 | 3.00 | 1.50 | 54.00 | M3 | | |
| | | 1 | 8.00 | 2.00 | 1.30 | 20.80 | M3 | | |
| | | 1 | 30.00 | 1.00 | 0.80 | 24.00 | M3 | | |
| | | 1 | 20.00 | 2.00 | 0.80 | 32.00 | M3 | | |
| | | 1 | 15.00 | 1.00 | 0.25 | 3.75 | M3 | | |
| | | 1 | 18.00 | 2.50 | 1.40 | 63.00 | M3 | | |
| | | 1 | 18.00 | 3.00 | 0.55 | 29.70 | M3 | | |
| | | 1 | 7.00 | 2.50 | 0.50 | 8.75 | M3 | | |
| | | 1 | 3.00 | 2.00 | 0.35 | 2.10 | M3 | | |
| | | 1 | 4.00 | 1.50 | 0.30 | 1.80 | M3 | | |
| | Less for H.P. | 0 | 0.00 | 0.00 | 0.00 | 0.00 | M3 | 2412.11 2442.64 | 1020081.20 |
| | | | | | | 422.90 | M3 | 2427.65 | 1026653.19 |
| 2 | Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job. | 0 | 2.50 | | | 0.00 | M | 2744.80 4159.56 | 0.00 |
| | | | | | | | | | 1026653.19 |
| | Add 1 % Contingency | | | | | | | | 10266.53 |
| | | | | | | | | Total | 1036919.72 |
| | | | | | | | | Say | 1036500.00 |

Chid
19/9/2020
J.E.

Chid
19.09.2020
A.E.

Chid
19/9/20
E.E. 1030281.20
Say Rs 10.303 Lacs

Technically Approved for Rs 24.81 Lacs (Rupees Twenty Four Lacs Eighty One Thousand)

Technically Approved for Rs 10.303 Lacs (Rupees Ten Lacs Thirty Three Thousand Three Hundred) only

Chid
24/9/2020
Superintending Engineer
RWD Work Circle-Swar
24/9/2020