

Inspection Report For Flood Damage Work

Date :

1 Name of PIUs :

Gopalganj - 2

2 Name of Block/Road :

Balla Ramdeo Pandey Ke ghar Se Holkar Baidh Pak
Balkunthpur

A For Road

1 Damage Location / Chainage :

50 m to 2000 m

2 Damage Length :

206 m

3 Nature of Damage :

Heavy Rain / Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works:

Brick Bats

ii Equipments / Tools being used in Restoration Works:

JCB, Tractor, Trolly, Bullock, Shovel

iii Procedure taken up in Restoration Works:

Yes

iv Restored Length:

206 m

B For Bridge

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

Phal
27/10/2020

25.10.2020
AE

09/11/20
EE

Signature
27/11/20

(Name of Inspector)



ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR

Balha Ramdeo Pandey Ke Ghar Se Hokar Budh Tak

ESTIMATED COST - RS.

1879800.00 1758500.00

SUBMITTED BY :-
EXECUTIVE ENGINEER
RWD (W) DIVISION
GOPALGANJ-2

Report

Name of Work :- **Motorable work of Balha Ramdeo Pandey Ke Ghar Se Hokar Budh Tak**

Estimated Cost :- ~~1879800.00~~ ~~1758500.00~~ = 0
1758500.00 = 00

Total length of Road :- **2.000 km**

Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.

P. K. Singh
27/11/20
J.E.




P. K. Singh
27-11-2020
A.E.

P. K. Singh
07/11/20
E.E.

**ed Estimate For Motorable Work in Road from Balha Ramdeo Pandey Ke C
Se Hokar Budh Tak damaged due to Heavy rain/flood for year 2020-2021**

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amou
Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
CH - 50 M to 2000 M	1	15.00	4.50	1.00	67.50	M3		
	1	7.00	3.00	1.50	31.50	M3		
	1	12.00	2.00	1.00	24.00	M3		
	1	9.00	4.00	1.50	54.00	M3		
	1	10.00	4.00	1.00	40.00	M3		
	1	21.00	4.00	2.00	168.00	M3		
	1	30.00	4.00	1.10	132.00	M3		
	1	20.00	4.00	0.50	40.00	M3		
	1	14.00	0.50	0.50	3.50	M3		
	2	30.00	4.00	0.60	144.00	M3		
	1	29.00	2.00	0.70	40.60	M3		
	1	9.00	1.20	2.00	21.60	M3		
Less for H.P.	0	1.23	1.23	0.95	0.00	M3		
					766.70	M3	2412.11	1729965.20
2 Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			0.00	M	4159.56	0.00
					711.20			1741110.58
								1741110.58
Add 1 % Contingency							1729965	1861279.26
							1729920	1861279
					1747264	20	Total	1879892.05
							Say	1879890.00

Say Rs 17472642
Rs 17.475 Lacs

 J.E.
 A.E.
 E.E.
Technically Approved for Rs 17.473 Lacs (Rupees Seventeen Lacs Forty Seven Thousand & Three Hundred only)
 RWD Work Circle, Siman
 11/01/21
 11/01/2021