



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

FDR



RESTORETION FOR LATE RAVIPRAKASH KE GHAR TO PURECHHAPRA TAK

DISTRICT	:-	Chapra	
DIVISION	:-	Sonpur	
BLOCK	:-	Parsa	
TOTAL LENGTH OF ROAD	:-	3.200	KM
TOTAL COST OF CONSTRUCTION	:-	3.985	Lac
TOTAL COST OF PROJECT	:-	3.985	Lac


FDR (2020-2021)


प्रतिवेदन

प्रमंडल का नाम:- ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर
पथ का नाम:- स्व० रवि प्रकाश के घर से पुरे छपरा तक।
पथ की लम्बाई:- 3.200 कि०मी०
प्राक्कलित राशि:- 3.985 लाख
प्रखंड:- परसा
जिला:- सारण

प्रस्तुत प्राक्कलन सारण जिला अन्तर्गत परसा प्रखंड के स्व० रवि प्रकाश के घर से पुरे छपरा तक पथ बाढ़ से क्षतिग्रस्त (FDR) पथांश का यातायात पुर्नस्थापन (Motrable) कार्य कराकर प्राक्कलन तैयार किया गया है। इस वर्ष अचानक अत्यधिक बाढ़ आने के कारण पथ में जगह जगह कटाव हो गया एवं पथ क्रस्ट बह गया जिससे आवागमन बाधित हो गया, चुनाव के मध्य नजर पथ का तत्काल मरम्मत के लिए पथांश में Brick Bats एवं मिटी भरकर कटाव से बचाव का कार्य करते हुए यातायात को पुर्नस्थापित किया गया।

पथ मरम्मत कार्य का प्राक्कलन वर्तमान अनुसूची दर पर ही तैयार किया गया है। प्राक्कलन की स्वीकृति अपेक्षित है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल परसा


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल परसा

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल सोनपुर

FDR

GENERAL ABSTRACT OF COST

Block:--

Parsa

District:- Chapra


Length of Road:--


3.200 KM

Name of Road:--

Restoretion For Late Raviprakash Ke Ghar To Purechhapra Tak

SL. No.	Item of Work	Amount
A	TOTAL COST OF CONSTRUCTION	: 3.985 Lacs
	TOTAL	: 3.985 Lacs


Junior Engineer


Asstt. Engineer


Executive Engineer

T/A Approved for Rs- 3.985 Lacs (Rupees Three lacs ninety
Eighty Thousand Five hundred) only

SE
RWD


S.E., Chapra

GENERAL ABSTRACT OF COST FOR FDR OF ROAD

NAME OF ROAD : Restoration For Late Raviprakash Ke Ghar To Purechhapra Tak
DISTRICT Chapra
BLOCK Parsa
DIVISION Sonpur
LENGTH OF ROAD (in Km) 3.200

Sl. No.	DESCRIPTION	Amount	1 % Labour Cess	12 % GST	GROSS AMOUNT (LAKHS)
PART-A	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL				
1	EARTHWORK / BRICK BATS	3.526	0.035	0.423	3.985
TOTAL COST OF PROJECT IN LACS =		3.526	0.035	0.423	3.985


22/12/20
JE
RWD


3/12/20
AE
RWD


07/12/20
EE
RWD

Inspection Report For Flood Damage Work

Date :- 25/12/2020
1 Name Of PIUs :- Executive Engineer, RWD, WORKS DIVISION-SONPUR
2 Name Of Road :- Restoration For Late Raviprakash Ke Ghar To Purechhapra Tak
3 Name Of Block :- Parsa

A.FOR ROAD

1 Damage Location/Chainage :- CH - 1722 M To 1741 M CH - 1945 M To 1961 M
CH - 2232 M To 2249.76 M
2 Damage Length :- 52.76
3 Nature Of Damage :- Wash Out Of Road Crust With Embankment
4 Details Of Restoration :-
i Material Being Used In Restoration :- EARTHWORK / BRICK BATS
ii Equipment/Tools Being Used In Restoration Works :- Tracter, Loader, Hambar
iii Procedure Taken Up In Restoration Works :- Filling Of Brick Bats In Wash Out Portion
Of Road Crust And Supporting By
Earthwork In Embankment
iv Restored Length :- 52.76

B.FOR ROAD

1 Damage Location/Chainage :-
2 Damage Length :-
3 Nature Of Damage
4 Details Of Restoration :-
i Material Being Used In Restoration :-
ii Equipment/Tools Being Used In Restoration Works :-
iii Procedure Taken Up In Restoration Works :-
iv Restored Length :-

Signature Of JE/AE/EE

Signature
(Name Of Inspector)

