

GOVERNMENT OF BIHAR

RURAL WORKS DEPARTMENT

Estimate of FDR

MMGSY (SC) UNDER CONSTRUCTION



NAME OF ROAD :

Kaituka Nandan (Maker - Jagdishpur) PMGSY Sadak se Tara Amna

DISTRICT

:

CHHAPRA

DIVISION

:

SONPUR

BLOCK

:

MAKER

TOTAL LEGTH OF ROAD

:

0.900

KM

TOTAL COST OF CONSTRUCTION

:

4.010

LAKH

TOTAL COST OF PROJECT

:

4.010

LAKH

SUBMITTED BY

Executive Engineer

Rural Works Department

Works division, Sonpur

तकनीकी प्रतिवेदन

योजना शीर्ष बाढ़ क्षतिग्रस्त मरम्मत
कार्य का नाम केंतुका नन्दन पी0एम0जी0एस0वाई0 सड़क से तारा अमनीर तक मोटरबुल कार्य।

प्राक्कलित राशि 4.01 लाख
प्रखण्ड का नाम मकर

प्रस्तुत प्राक्कलन कार्यपालक अभियंता के निर्देश के आलोक में सारण जिला अन्तर्गत मकर प्रखण्ड में केंतुका नन्दन (मकर जगदीशपुर) पी0एम0जी0एस0वाई0 सड़क से तारा अमनीर पथ का बाढ़ से क्षतिग्रस्त पथांश का पुनर्स्थापन कार्य का बनाया गया है।


पथ में चैनेज सं0 550 मी0 से 560 मी0 में बाढ़ के पानी का तेज धारा के कारण पथ में कटाव हो गया है। चैनेज सं0 560 मी0 से 650 मी0 में किये गये मेटल का कार्य बह गया है।

प्रस्तुत प्राक्कलन में पथ के कटे हुए पथांश में Brick Bats भरकर तथा उसके ऊपर GSB एवं WBM Gr- 3 कार्य एवं चैनेज सं0 560 मी0 से 650 मी0 में WBM Gr- 3 कार्य किया गया है। सभी मदों का दर वर्तमान स्वीकृत नये अनुसूचित दर पर तैयार किया गया है।

अतः प्रस्तुत प्राक्कलन जनहित एवं लोकहित में यथाशीघ्र स्वीकृति अपेक्षित है।


10/12/2020

कनीय अभियंता
ग्रा0 का0 वि0
कार्य प्रशाखा
मकर


10/12/20

सहायक अभियंता
ग्रा0 का0 वि0
कार्य अवर प्रमंडल
मकर

कार्यपालक अभियंता
ग्रा0 का0 वि0
कार्य प्रमंडल
सोनपुर

Inspection Report for flood damage work

Date :

1. Name of PIUs : RWD, WORKS Division Sonapur
2. Name of Block/Road : Makel, Kailene Nandou (Makel-Ingdishpur) PMGS

(A) For Road -

Road to Tada Anwar.

1. Damage Location/Chainage : 550-560 M, 560-650 M
2. Damage Length : 100.00 M
3. Nature of Damage : Wash out the Road.
4. Details of Restoration :

(i) Material being used in Restoration : B-batts, G.S.R., W.B.M.-gr. etc.

(ii) Equipment/Tools being used in Restoration works:

(iii) Procedure taken up in Restoration works :

(iv) Restored Length : 100.00 M

(B) For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration:

(i) Material being used in Restoration :

(ii) Equipment/Tools being used in Restoration works :

(iii) Procedure taken up in Restoration works :

(iv) Restored Length :

Signature Of JE/AE/EE

Signature
(Name Of Inspector)

Abstract of cost

Name of Road :- Kaituka Nandan (Maker - Jagdishpur) PMGSY Sadak se Tara Amnaur

Name of Distt:- Chhapra

Block:- Maker

Length of Road :- 0.900 KM

Sl. No.	Description of items	Amount (in Lakh)
1	Brick Bats	220820.00
2	GSB	14492.00
3	WBM Gr- 3	119219.00
	Sub Total Cost	354531.00
1	Add GST 12%	42544.00
2	Add Labour Cess 1%	3545.00
	Total Cost of Project	400620.00
	Total Cost of Project in Lakh	4.01

[Signature]
15/12/2020
Junior Engineer
RWD, Works Section
Maker

[Signature]
15.12.20
A.E.
Junior Engineer
RWD, Works Sub division
Maker

E.E.
Junior Engineer
RWD, Works Division
Sonpur

r A approved for Rs 4.01 Lakh (Rupees four Lakhs and thousand only)

[Signature]
15/12/20
S.E. Chhapra