

## Inspection Report For Flood Damage Work

Date:

1 Name of PIUs: Gopalgarh - 2

2 Name of Block/Road: Baikunthpur / REO Road Dighua Matia To Kachhari  
Tola Raq**A For Road**

1 Damage Location / Chainage: 100 m to 1500 m

2 Damage Length: 383 m

3 Nature of Damage: Heavy Rain / Flood

**4 Details of Restoration Works:**

i. Material being used in Restoration Works: Brick Bats

ii Equipments / Tools being used in Restoration Works: JCB, Tractor, Trolly, Shovel, Batching  
Roller

iii Procedure taken up in Restoration Works: Yes

iv Restored Length: 383 m

**B For Bridge**

N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

**4 Details of Restoration Works:**

i. Material being used in Restoration Works:

ii Equipments / Tools being used in Restoration Works:

iii Procedure taken up in Restoration Works:

iv Restored Length:

P.D. J.E. 25/9/2022

AE

EE

Signature  
(Name of Inspector)  
R.W.D. W.D.  
Hathua



# ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

## FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR  
DISTRICT :- GOPALGANJ  
BLOCK :- BAIKUNTHPUR

REO Road Dighwa Math To Kachhari Tola Tak

ESTIMATED COST - RS. 1578800.00

SUBMITTED BY :-  
EXECUTIVE ENGINEER  
RWD (W) DIVISION  
GOPALGANJ-2

## Report

Name of Work :- Motorable work of REO Road Dighwa Math To Kachhari Tola Tak

Estimated Cost :- 1578800.00


Total length of Road :- 1.761 km


Description :- The present estimate has been farmed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transporation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road. Hence there has been a provision of laying R.C.C. NP3 1000 MM Dia hume pipe.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.

  
14/9/2020  
J.E.

  
13.09.2020  
A.E.

  
19/9/20  
E.E.



# ailed Estimate For Motorable Work in Road from REO Road Dighwa Math To Kachhari Tola Tak damaged due to Heavy rain/flood for year 2020-2021

Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
Providing brick bats billed in latches including all cost of labour & material with all complete job.								
CH -100 M to 1500 M	1	4.00	0.60	0.25	0.60	M3		
	1	20.00	1.50	0.50	15.00	M3		
	1	26.00	1.20	0.50	15.60	M3		
	1	20.00	1.80	0.30	10.80	M3		
	1	28.00	1.20	0.45	15.12	M3		
	1	15.00	1.00	0.70	10.50	M3		
	1	24.00	1.20	1.40	40.32	M3		
	1	30.00	2.35	1.70	119.85	M3		
	1	23.00	1.20	1.10	30.36	M3		
	1	25.00	1.20	1.20	36.00	M3		
	3	30.00	2.00	1.20	216.00	M3		
	1	27.00	2.00	1.10	59.40	M3		
	1	25.00	2.00	0.50	25.00	M3		
	1	26.00	1.50	1.20	46.80	M3		
Less for H.P.	0.79	1.23	1.23	5.00	5.98	M3	2412.11	1532582
					635.37		2427.65	1542465.80
Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	2	2.50			5.00	M	2744.50 4159.56	137232 20797.80
								1546305
								1563263.60
Add 1 % Contingency								1546305 15632.64
							Total	1578896.24
							Say	1578800.00

Rs 15617682  
Say Rs 15.61862

*[Signature]*  
18/19/2020  
J.E.

*[Signature]*  
19.03.2020  
A.E.

*[Signature]*  
19/19/20  
E.E.

Technically Approved for Rs 15.61862 (Rupees Fifteen Lacs Sixty one Thousand & Eight Hundred) only

*[Signature]*  
Superintending Engineer  
Rd. W.D. Work Circle Siwar