

## Inspection Report For Flood Damage Work

Date :

1 Name of PIUs: UDALWANT-22 Name of Block/Road: BARKUNTHIPUR/UTAMHARI BANDH WATI RAY ICE TOLA TO SONWALIYA PASCHIM TOLA**A For Road**1 Damage Location / Chainage: 220 m to 450 m2 Damage Length: 234 m3 Nature of Damage: Heavy Rain / Flood.

## 4 Details of Restoration Works:

i. Material being used in Restoration Works: Brick Batsii Equipments / Tools being used in Restoration Works: DCB, Tractor, Trolly, Beldag, Shovel.iii Procedure taken up in Restoration Works: Yesiv Restored Length: 234 m**B For Bridge**N/A

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

## 4 Details of Restoration Works:

i. Material being used in Restoration Works :

ii Equipments / Tools being used in Restoration Works :

iii Procedure taken up in Restoration Works:

iv Restored Length :

*[Signature]*  
25/9/2020

*[Signature]*  
25.09.2020  
AE

*[Signature]*  
25/9/20  
EE

*[Signature]*  
16/12/20  
Signature  
(Name of Inspector)

(80)

(02)



# ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

## FLOOD DAMAGED REPAIR (F.D.R.)

STATE :- BIHAR  
DISTRICT :- GOPALGANJ  
BLOCK :- BAIKUNTHPUR

Gamhari Bandh Gati Rai Ke Tola to Sonwaliya Paschim Tola

ESTIMATED COST - RS. ~~2500000.00~~ 2344800.00

SUBMITTED BY :-  
EXECUTIVE ENGINEER  
RWD (W) DIVISION  
GOPALGANJ-2

## Report

**Name of Work** :- Motorable work of Gamhari Bandh Gati Rai Ke Tola to Sonwaliya Paschim Tola

**Estimated Cost** :- ~~2500000.00~~ Rs 2344800.00


**Total length of Road** :- 0.450 km

**Description** :- The present estimate has been framed under the supervision of Assistant engineer in accordance with the order of Executive Engineer, RWD, WD Gopalganj-2, letter No. - 1574 dated 18-08-2020. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transportation has been obstructed. The immediate motorable work is necessary in public interest. Villagers will be benefitted by the completion of this motorable work.

In the estimate there has been a provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per the specifications. The estimate is devoted to technical and administrative acceptance.

  
19/9/2020  
J.E.

  
18.09.2020  
A.E.

  
19/9/20  
E.E.



# Detailed Estimate For Motorable Work in Road from Gamhari Bandh Gati Rai Ke Tola to Sonwaliya Paschim Tola damaged due to Heavy rain/flood for year 2020-2021

r.	Items	No.	L (M.)	W (M.)	D (M.)	Qty.	Unit	Rate	Amount
	Providing brick bats billed in ditches including all cost of labour & material with all complete job.								
	CH - 220 M to 450 M	1	15.00	3.00	1.60	72.00	M3		
		1	7.00	1.00	2.00	14.00	M3		
		1	25.00	4.00	2.00	200.00	M3		
		1	7.00	1.50	2.50	26.25	M3		
		1	<del>15.00</del> 20.00	<del>1.00</del> 1.35	2.00	<del>20.00</del> 54.00	M3		
		1	30.00	1.00	3.00	90.00	M3		
		1	14.00	1.50	2.50	52.50	M3		
		1	29.00	1.55	3.00	134.85	M3		
		2	30.00	2.00	1.20	144.00	M3		
		1	<del>25.00</del> 16.00	1.50	3.00	<del>112.50</del> 40.92	M3		
		1	<del>20.00</del> 5.00	<del>1.70</del> 4.00	1.80	<del>61.20</del> 35.00	M3		
		1	4.00	4.00	0.80	12.80	M3		
		1	3.00	3.75	0.50	5.63	M3		
	Less for H.P.	0	1.23	1.23	0.95	0.00	M3	2412.11	230682.12
						1019.73	M3	2427.65	2475535.40
	Providing & laying 1000 MM Dia NP3 Hume Pipe in single row -do-do- complete job.	0	2.50			956.35	M	4159.56	2321670.96
						0.00	M		0.00
									2321670.96
	Add 1 % Contingency							230682.11	2475535.40
								230682.11	2321670.96
						2329889.21	Total		2500290.75
							Say		2500000.00

Rs 23,29,889.21 (Rupees Twenty Three Lacs and Twenty Nine Thousand Eight Hundred Eighty Nine and 21/100 only)

*[Signature]*  
19/9/2020

J.E.

*[Signature]*  
19.09.2020

A.E.

*[Signature]*  
19/9/20

E.E.

Technically Approved for Rs 23.299 Lacs (Rupees Twenty Three Lacs and Twenty Nine Thousand Eight Hundred Eighty Nine and 21/100 only)

*[Signature]*  
13/11/21  
Superintending Engineer  
RWD Work, Circle-Siwan

*[Signature]*  
11/11/21