



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

FDR



RESTORETION FOR BANKERVA BHAV TO KUWARI AAZAM

DISTRICT	:-	Chapra	
DIVISION	:-	Sonpur	
BLOCK	:-	Parsa	
TOTAL LENGTH OF ROAD	:-	4.200	KM
TOTAL COST OF CONSTRUCTION	:-	13.988	Lac
TOTAL COST OF PROJECT	:-	13.988	Lac


FDR (2020-2021)


प्रतिवेदन


प्रमंडल का नाम:—	ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर
पथ का नाम:—	बनकेरवों भाव से कुआरी आजम
पथ की लम्बाई:—	4.200 कि०मी०
प्राक्कलित राशि:—	13.988 लाख
प्रखंड:—	परसा
जिला:—	सारण

प्रस्तुत प्राक्कलन सारण जिला अन्तर्गत परसा प्रखंड के बनकेरवों भाव से कुआरी आजम तक पथ बाढ़ से क्षतिग्रस्त (FDR) पथांश का यातायात पुर्नस्थापन (Motrable) कार्य कराकर प्राक्कलन तैयार किया गया है। इस वर्ष अचानक अत्यधिक बाढ़ आने के कारण पथ में जगह जगह कटाव हो गया एवं पथ क्रस्ट बह गया जिससे आवागमन बाधित हो गया, चुनाव के मध्य नजर पथ का तत्काल मरम्मत के लिए पथांश में Brick Bats एवं मिटी भरकर कटाव से बचाव का कार्य करते हुए यातायात को पुर्नस्थापित किया गया।

पथ मरम्मत कार्य का प्राक्कलन वर्तमान अनुसूची दर पर ही तैयार किया गया है। प्राक्कलन की स्वीकृति अपेक्षित है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल परसा


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल परसा


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल सोनपुर

Inspection Report For Flood Damage Work

Date :- 2-12-20
Name Of PIUs :- Executive Engineer, RWD, WORKS DIVISION-SONPUR
Name Of Road :- Restoration For Bankerva bhav To kuwari Aazam
Name Of Block Parsa

A.FOR ROAD

Damage Location/Chainage :- CH-1550 M TO 1556.1 M CH-1830 M TO 1842.2 M
CH-1700 M TO 1712.13 M CH-2150 M TO 2165.24 M
CH-2150 M TO 2165.24 M CH-3135 M 3157.4 TO M

2 Damage Length :- 69.28

3 Nature Of Damage :- Wash Out Of Road Crust With Embankment

4 Details Of Restoration :-

- i Material Being Used In Restoration :- EARTHWORK / BRICK BATS
- ii Equipment/Tools Being Used In Restoration Works :- Tracter, Loader, Hambar
- iii Procedurre Taken Up In Restoration Works :- Filling Of Brick Bats In Wash Out Portion
Of Road Crust And Supporting By
Erthwork In Embankment
- iv Restored Length :- 69.28

B.FOR ROAD

1 Damage Location/Chainage :-

2 Damage Length :-

3 Nature Of Damage

4 Details Of Restoration :-

- i Material Being Used In Restoration :-
- ii Equipment/Tools Being Used In Restoration Works :-

Signature Of JE/AE/EE

Signature
(Name Of Inspector)

02/12/2020
G.E


FDR


GENERAL ABSTRACT OF COST

Block:- Parsa District:- Chapra
Length of Road:- 4.200 KM
Name of Road:- Restoration For Bankerva bhav To kuwari Aazam


SL. No.	Item of Work	Amount
A	TOTAL COST OF CONSTRUCTION :	13.988 Lacs
	TOTAL :	13.988 Lacs


Junior Engineer


Asstt. Engineer


Executive Engineer

T/A Approved for Rs. 13,988 (Rupees Thirteen lacs ninety eight Thousand eight hundred) only.
SE
RWD


S.E. Chapra

GENERAL ABSTRACT OF COST FOR FDR OF ROAD

NAME OF ROAD : Restoration For Bankerva bhav To kuwari Aazam
DISTRICT Chapra
BLOCK Parsa
DIVISION Sonpur
LENGTH OF ROAD (in Km) 4.200

Sl. No.	DESCRIPTION	Amount	1 % Labour Cess	12 % GST	GROSS AMOUNT (LAKHS)
PART-A	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL				
1	EARTHWORK / BRICK BATS	12.379	0.124	1.485	13.988
TOTAL COST OF PROJECT IN LACS =		12.379	0.124	1.485	13.988


15/11/20

JE
RWD


15/11/20

AE
RWD


15/11/20

EE
RWD

