


FDR (2020-2021)


प्रतिवेदन


प्रमंडल का नाम:-	ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर
पथ का नाम:-	ब्रहमारर मिडिल स्कूल से पी0एम0जी0एस0वाई0 नसोचक
पथ की लम्बाई:-	1.350 कि0मी0
प्राक्कलित राशि:-	5.587 लाख
प्रखंड:-	परसा
जिला:-	सारण

प्रस्तुत प्राक्कलन सारण जिला अन्तर्गत परसा प्रखंड के ब्रहमारर मिडिल स्कूल से पी0एम0जी0एस0वाई0 नसोचक तक पथ बाढ़ से क्षतिग्रस्त (FDR) पथांश का यातायात पूर्णस्थापन (Motrable) कार्य कराकर प्राक्कलन तैयार किया गया है। इस वर्ष अचानक अत्यधिक बाढ़ आने के कारण पथ में जगह जगह कटाव हो गया एवं पथ क्रस्ट बह गया जिससे आवागमन बाधित हो गया। चुनाव के मध्य नजर पथ का तत्काल मरम्मत के लिए पथांश में Brick Bats एवं मिटी भरकर कटाव से बचाव का कार्य करते हुए यातायात को पुर्नस्थापित किया गया।

पथ मरम्मत कार्य का प्राक्कलन वर्तमान अनुसूची दर पर ही तैयार किया गया है। प्राक्कलन की स्वीकृति अपेक्षित है।


क.नीय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल परसा


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल परसा


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल सोनपुर

Inspection Report For Flood Damage Work

Date :-

03-12-20

1 Name Of PIUs :-

Executive Engineer, RWD, WORKS DIVISION-SONPUR

2 Name Of Road :-

Restoration For Bahamara Middle School To PMGSY Nasochak

3 Name Of Block

Parsa

A.FOR ROAD

1 Damage Location/Chainage :- CH-200 M TO 212.2 M CH-400 M TO 403.66 M
CH-550 M TO 554.27 M

2 Damage Length m :- 20.13

3 Nature Of Damage :- Wash Out Of Road Crust With Embankment

4 Details Of Restoration :-

i Material Being Used In Restoration :-

EARTHWORK / BRICK BATS

ii Equipment/Tools Being Used In Restoration Works :-

Tracter, Loader, Hambar

iii Procedure Taken Up In Restoration Works :-

Filling Of Brick Bats In Wash Out Portion
Of Road Crust And Supporting By
Earthwork In Embankment

iv Restored Length m :-

20.13

B.FOR ROAD

1 Damage Location/Chainage :-

2 Damage Length :-

3 Nature Of Damage

4 Details Of Restoration :-

i Material Being Used In Restoration :-

ii Equipment/Tools Being Used In Restoration Works :-

iii Procedure Taken Up In Restoration Works :-

iv Restored Length :-

Signature Of JE/AE/EE

Signature
(Name Of Inspector)

FDR

GENERAL ABSTRACT OF COST

Block:-

Parsa

District:- Chapra

Length of Road:-

1.350 KM

Name of Road:-

Restoration For Bahamara Middle School To PMGSY Nasochak

SL. No.	Item of Work	Amount
A	TOTAL COST OF CONSTRUCTION	5.587 Lacs
	TOTAL	5.587 Lacs

Junior Engineer

Asstt. Engineer

Executive Engineer

T/A Approved for Rs- 5.587 lacs (Five lacs fifty eight thousand seven hundred) only

SE
RWD

S. E. Chapra


GENERAL ABSTRACT OF COST FOR FDR OF ROAD

NAME OF ROAD : Restoration For Bahamara Middle School To PMGSY Nasochak
DISTRICT : Chapra
BLOCK : Parsa
DIVISION : Sonpur
LENGTH OF ROAD (in Km) 1.350

Sl. No.	DESCRIPTION	Amount	1 % Labour Cess	12 % GST	GROSS AMOUNT (LAKHS)
PART -A	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL				
1	EARTHWORK / BRICK BATS	4.944	0.049	0.593	5.587
TOTAL COST OF PROJECT IN LACS =		4.944	0.049	0.593	5.587


JE
RWD


AE
RWD


EE
RWD

