RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:-

BHANGOLDIH TO BHANTIYA

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

FORBESGANJ

ESTIMATED COST

575166.00

Inspection Report for flood damage work

1.Name of PIUs-

RWD forbesgay

2.Name of Block/Road-

For besgaij

A.For Road

Date:

Bhangoldin to Bhantigg.

1.Damage Location/Chainage:

2. Damage Lengh

12m+12m = 24 m

3. Nature of Damage 4. Details of Restoration

flood damage diter up to 3m.

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: iii Procedure taken up in Restoration works

iv Restored Length

B. For Bridge

1.Damage Location/Chainage:

2. Damage Lengh

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: Local sand, Bleats and bankers pile.

filly all call properly in dange one

24 m.

Signature of JE/AE/EE

(Name of Inspector)

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2019 in ARARIA District

Name of Road:-

BHANGOLDIH TO BHANTIYA

Block: FORBESGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION

Rs

260691.00

COST OF 2ND CUTTING RESTORATION

314475.00

TOTAL COST OF RESTORATION

Rs

575166.00

Say

Rs

575166.00

Technically Approved for Rs. 575166.00 (Rupeas Severty Fine Howard one handred Sixty SIx Josly.

Superintending Engineer Rural Works Department Works Circle, Kishanganj

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM BHANGOL DIH TO BHANTIYA CUTTING-1

Block: FORBESGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate	Amount
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.		(1115)	(Rs)	(Rs)
		Cum	155.00	627.77	97304,59
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	156.00	75.86	11833.94
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	78.00	40.06	3124.72
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				3124.72
		Each	2627.44	37.35	00125.42
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	Lucii	2027.44	37.33	98126.12

6	Supply, laying and Carriage of of hume pipe 1000	Cum	11.96	1870.43	22370.38	
	mm dia (HPC), all complete job.					
		meter	0.00	5382.71	0.00	
_	TOTAL AMOUNT =					
	27931.00					
	SAY TOTAL AMOUNT =					

RWD WORKS

DIV. FORBESGANJ RWD WORKS DIV. FORBESGANJ

RWD WORKS DIV. FORBESGANJ

Technically Approved for R. 260691.00 (Assess two land Staty Housand Six hyndred Ningy one Jonly.