

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM GOPALPUR TO
MANJHUA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

4723309.00

Inspection Report for flood damage work

Date:

1. Name of PIUs-

R.W.D. Farbesganj

2. Name of Block/Road-

Farbesganj

A. For Road

Gopalpur to Manshua

1. Damage Location/Chainage :

2. Damage Length : 164.0m

3. Nature of Damage : Flood Damage Road

4. Details of Restoration :

i Material being used in Restoration

: Local Sand, B/safes and bamboo pile

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: Filling all cut properly

iv Restored Length

: 164.0m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE



Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM GOPALPUR TO MANJHUA

Block: FORBESGANJ


District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	3344.61	627.77	2099651.73
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	1536.00	75.86	116518.81
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	384.00	40.06	15383.26
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	38785.11	37.35	1448496.67
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	157.70	1870.43	294967.24


6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	45.00	5382.71	242221.84
	TOTAL AMOUNT =				4217240.00
	ADD 12.00 %GST=				506069.00
	SAY TOTAL AMOUNT =				4723309.00


 6/11/20
 RWD WORKS
 DIV.
 FORBESGANJ


 3/11/2020
 AE
 RWD WORKS DIV. FORBESGANJ


 B.E.
 RWD WORKS
 DIV. FORBESGANJ

*Technically Approved for Rs. 4723309.00 (Rupees forty seven
 Lacs twenty three thousand three hundred Nine) only.*


Superintending Engineer
 Rural Works Department
 Works Circle, Kishanganj