

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM GHORAGHAT TO
CHIKNI ROAD

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

9820487.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- Ghoraghat to Chikni Road

2. Name of Block/Road- Forbesganj

A. For Road Ghoraghat to Chikni Road

1. Damage Location/Chainage :

2. Damage Length : 440m + 60m + 160m + 32m = 252m

3. Nature of Damage :

4. Details of Restoration : Flood damage ditch up to 3.5m depth

i Material being used in Restoration

: Local sand, Blat and bamboo pile

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: Filling all cuts properly in damaged area

iv Restored Length

: 252m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:


iii Procedure taken up in Restoration works

iv Restored Length

} N/A



Signature of JE/AE/EE



Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

GHORAGHAT TO CHIKNI ROAD

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ


Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION	Rs	886907.00
COST OF 2ND CUTTING RESTORATION	Rs	5875521.00
COST OF 2ND CUTTING RESTORATION	Rs	3058059.00

TOTAL COST OF RESTORATION Rs 9820487.00

Say Rs 9820487.00


J.E.


A.E.


E.E.

Technically Approved for Rs. 9820487.00 (Rupees Ninety Eight Lacs twenty thousand four hundred eighty seven) only.


SuperIntending Engineer
Rural Works Department
Works Circle, Kishangj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM GHORAGHAT TO CHIKNI ROAD CUTTING-1

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	490.00	627.77	307608.06
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	783.00	75.86	59397.29
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	360.00	40.06	14421.81
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	8466.18	37.35	316184.15
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	50.40	1870.43	94269.81
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				791881.00
	ADD 12.00 %GST=				95026.00
	SAY TOTAL AMOUNT =				886907.00

JE 10/11/20
RWD WORKS
DIV.
FORBESGANJ

AE
RWD WORKS DIV. FORBESGANJ

E.E.
RWD WORKS
DIV. FORBESGANJ

Technically Approved for Rs. 886907.00 (Rupees Eight
Lacs Eighty Six thousand Nine hundred Seven) only.