RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

RESTORATION OF ROAD FROM AMHARA TO RAJPUT

NAME OF ROAD:- TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

569855.00

Inspection Report for flood damage work

Date:

1. Name of PlUs- E.E. R. W. D Forbergars

2. Name of Block/Road - Forbergari/ Amhora to Rasput Joly

A.For Road

1. Damage Location/Chainage:

2. Damage Lengh

45m+ 42m+ 65m =152m

3. Nature of Damage

Flood damaye deaten a. in malpth.

4. Details of Restoration

i Material being used in Restoration

: local land, Bambo Hlyg, B/bot, Ec by

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: Alling all cuts property indange and

iv Restored Length

B. For Bridge

1.Damage Location/Chainage:

2. Damage Lengh

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

. M. A

Signature

(Name of Inspector)

Signature of FACIETY

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM AMHARA TO RAJPUT TOLA

Block: FORBESGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	266.00	627.77	166987.23
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.			10	
		Mtr.	0.00	75.86	0.00
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	0.00	40.06	0.00
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	8051.82	37.35	300709.07
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	21.98	1870.43	41102.76

6	Supply,laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
1		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				508799.00
	ADD 12.00 %GST=				61056.00
	SAY TOTAL AMOUNT =	-			569855.00

RWD WORKS

DIV. FORBESGANJ **RWD WORKS DIV. FORBESGANJ**

RWD WORKS DIV. FORBESGANJ

Technically Approved for Re. 5-69855.00 (Rupees fine land Sixty Nine Housand Eight-hundred Lifty Fine only.

Superintending Engineer Rural Works Department Works Circle, Kishanganj