

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:-

RESTORATION OF ROAD FROM DEOPURA TO
HARIZAN TOLA

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

FORBESGANJ

ESTIMATED COST

4666404.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- R W D Forbesganj

2. Name of Block/Road- Forbesganj

A. For Road : Deopura to horizan Tola.

1. Damage Location/Chainage :

2. Damage Length : $30m + 52 + 42m + 30 + 65m = 219m$

3. Nature of Damage :

4. Details of Restoration : Flood damage ditch and side cutting

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: Local Sand, B/Bats and Bamboo pit

iii Procedure taken up in Restoration works

iv Restored Length : Filling all cuts properly in damp area.
219m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: }

iii Procedure taken up in Restoration works

iv Restored Length : N/A.

Signature of JE/ADEE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

DEOPURA TO HARIZAN TOLA

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION

Rs 2037584.00

COST OF 2ND CUTTING RESTORATION

Rs 2628820.00


TOTAL COST OF RESTORATION

Rs 4666404.00

Say


Rs 4666404.00


J.E.


A.E.


E.E.

Technically ~~Approved~~ Approval for Rs 4666404.00 (Rupees
fourty six Lacs sixty six thousand four hundred
and four) only


S.E.

RWD (W) circle
Kishanganj.

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM DEOPURA TO HARIZAN TOLA CUTTING-1

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1069.00	627.77	671087.80
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	1521.00	75.86	115380.93
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	486.00	40.06	19469.44
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	16673.27	37.35	622691.98
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	79.35	1870.43	148418.84
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	45.00	5382.71	242221.84
	TOTAL AMOUNT =				1819271.00
	ADD 12.00 %GST=				218313.00
	SAY TOTAL AMOUNT =				2037584.00

JE 10/3/11/20
RWD WORKS
DIV.
FORBESGANJ

AE 3/11/20
RWD WORKS DIV. FORBESGANJ

E.E.
RWD WORKS
DIV. FORBESGANJ

Technically approved for Rs:- 2037584.00 (Rupees twenty Lacs thirty seven thousand five hundred eighty four only)

Superintending Engineer
Rural Works Department
Works Circle, Kishanganj