

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM KHAIRKHA TO
HARIZAN TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

1819686.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- R.W.D. Farbesganj

2. Name of Block/Road- Farbesganj

A. For Road

Khairkha to Harizan talu.

1. Damage Location/Chainage :

2. Damage Length : $30.0 + 26.0 + 29.0 = 85.0m$

3. Nature of Damage : Flood damage water.

4. Details of Restoration :

i Material being used in Restoration :

Local Sand, B/bats, and Bamboo Piles.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

Filling all cuts properly in water area.

iv Restored Length :

85.0m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

N.A

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

KHAIRKHA TO HARIZAN TOLA

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ


Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION	Rs	668818.00
COST OF 2ND CUTTING RESTORATION	Rs	518146.00
COST OF 2ND CUTTING RESTORATION	Rs	632722.00

TOTAL COST OF RESTORATION Rs 1819686.00


Say Rs 1819686.00


J.E. 03/11/2020


A.E. 3/11/2020


J.E. 03/11/2020

Technically Approved for Rs. 1819686.00 (Rupees Eighteen
Lacs Nineteen Thousand Six hundred Eighty Six) only.


Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood In JULY 2019 In ARARIA District

Name of Road:

RESTORATION OF ROAD FROM KHAIRKHA TO HARIZAN TOLA CUTTING-1

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	396.77	627.77	249078.83
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	540.00	75.86	40963.65
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	180.00	40.06	7210.90
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	6678.07	37.35	249403.88
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	27.00	1870.43	50501.68
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				597159.00
	ADD 12.00 %GST=				71659.00
	SAY TOTAL AMOUNT =				668818.00

[Signature]
JE
10/3/17/2020

RWD WORKS
DIV.
FORBESGANJ

[Signature]
AE
3/11/2020

RWD WORKS DIV. FORBESGANJ

[Signature]
F.E.
3/11/20

RWD WORKS
DIV. FORBESGANJ

Technically Approved for Rs. 668818.00 (Rupees Six Lacs Sixty Eight Thousand Eight hundred Eighteen) only.