

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM KURSAKATTA HUTTA
CHOWK TO DONGRA BANDH

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

9123401.00

Inspection Report for flood damage work

Date:

1. Name of PIUs-

R.W.D. Forbesgar.

2. Name of Block/Road-

Forbesgar.

A. For Road

Kura Katta Hetta Check via Donga Bendi.

1. Damage Location/Chainage : 4.9 km, 3.20 km

2. Damage Length : 200m + 86m = 286m.

3. Nature of Damage : Flood damage ditch washed.

4. Details of Restoration :

i Material being used in Restoration

: Local Sand, Blasts and Bomber
Pile.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: Filling all cuts properly in
damage area.

iv Restored Length

: 286m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N/A.

Signature of JE/AE/EE

5/11/2020
J-E

5/11/2020
for

Signature

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

KURSAKATTA HUTTA CHOWK TO DONGRA BANDH

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION

Rs 5355597.00

COST OF 2ND CUTTING RESTORATION

Rs 3767804.00

TOTAL COST OF RESTORATION

Rs 9123401.00

Say

Rs 9123401.00

[Signature]
05/11/2020

[Signature]
6/11/2020
A.E

[Signature]
E.E
01/11/20

Technically approved for RS 9123401 (Rupees ninety one lac twenty three thousand four hundred one) only.

[Signature]
Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM KURSAKATTA HUTTA CHOWK TO DONGRA BANDH CH^{5.5}~~4.9~~ K.M.

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	3000.00	627.77	1883314.68
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	2700.00	75.86	204818.23
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	900.00	40.06	36054.52
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	38316.78	37.35	1431005.87
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	368.00	1870.43	688319.24
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	100.00	5382.71	538270.75
	TOTAL AMOUNT =				4781783.00
	ADD 12.00 %GST =				573814.00
	SAY TOTAL AMOUNT =				5355597.00

JE
RWD WORKS
DIV.
FORBESGANJ

AE
RWD WORKS DIV. FORBESGANJ

E.E.
RWD WORKS
DIV. FORBESGANJ