

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM HARIPUR TO DAK

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

1321625.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD Forbesganj

2. Name of Block/Road- Forbesganj

A. For Road Haripur to daak.

1. Damage Location/Chainage :

2. Damage Length : 40m + 15m = 55m

3. Nature of Damage : Flood damage ditches up to 5.5m depth

4. Details of Restoration :

i Material being used in Restoration

: Local Sand, Brickbat, eebang
bamboo piling etc.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: filled all cuts properly of damaged area.
55m

iv Restored Length

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

} N/A

Signature of JE/AE/EE

C
5/11/20
Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

HARIPUR TO DAK

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION

Rs 903222.00

COST OF 2ND CUTTING RESTORATION


Rs 418403.00

TOTAL COST OF RESTORATION

Rs 1321625.00


Say Rs 1321625.00


J.E.


A.E.


S.E.

Technically approved for Rs - 1321625.00 (Thirteen Lac twenty one thousand six hundred twenty five) only.


Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM HARIPUR TO DAK

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	478.50	627.77	300388.69
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	720.00	75.86	54618.19
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	240.00	40.06	9614.54
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	8946.47	37.35	334121.19
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	36.00	1870.43	67335.58

6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	7.50	5382.71	40370.31
	TOTAL AMOUNT =				806448.00
	ADD 12.00 %GST=				96774.00
	SAY TOTAL AMOUNT =				903222.00

[Signature]
JE
11/11/20

RWD WORKS
DIV.
FORBESGANJ

[Signature]
AE
11/11/2020

RWD WORKS DIV. FORBESGANJ

[Signature]
E.E.
11/11/20

RWD WORKS
DIV. FORBESGANJ