

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:-

RESTORATION OF ROAD FROM RANIGANJ
FORBESGANJ ROAD TO LAXMIPUR

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

FORBESGANJ

ESTIMATED COST

9737478.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD Forbesganj

2. Name of Block/Road- Forbesganj

A. For Road Ramiganj Forbesganj to Laxmipur

1. Damage Location/Chainage :

2. Damage Length : 299 m (45+198+56m)

3. Nature of Damage : Flood damage Road

4. Details of Restoration :

i Material being used in Restoration

: Local sand, Brickball, Bamboo Pili

ii Equipment/Tools being used in Restoration works:

: Ec baguete

iii Procedure taken up in Restoration works

: Filled all cuts properly damaged area
299m

iv Restored Length

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

:

ii Equipment/Tools being used in Restoration works:

:

iii Procedure taken up in Restoration works

:

iv Restored Length

:

} N/A

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 In ARARIA District

RESTORATION OF ROAD FROM RANIGANJ FORBESGANJ ROAD TO LAXMIPUR

Name of Road:-

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ


Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION	Rs	1401622.00
COST OF 2ND CUTTING RESTORATION	Rs	4920499.00
COST OF 2ND CUTTING RESTORATION	Rs	3415357.00

TOTAL COST OF RESTORATION Rs 9737478.00


Say Rs 9737478.00


J.E.


A.E.


E.E.

Technically Approved for Rs: 97,37,478.00 (Rupees Ninety seven Lacs thirty seven thousand four hundred seventy eight only)


Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM RANIGANJ FORBESGANJ ROAD TO LAXMIPUR CUTTING-1

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	731.25	627.77	459057.95
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	810.00	75.86	61445.47
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	270.00	40.06	10816.35
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	15600.40	37.35	582623.82
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
		Cum	74.25	1851.91	137504.58

6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				1251448.00
	ADD 12.00 %GST=				150174.00
	SAY TOTAL AMOUNT =				1401622.00

[Signature]
10/5/17/20

JE

RWD WORKS
DIV.
FORBESGANJ

[Signature]
8/11/2020

AE

RWD WORKS DIV. FORBESGANJ

[Signature]
E.EP

RWD WORKS
DIV. FORBESGANJ