RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM KUSMAHA TO HALL

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

3918962.00

<u>Insp</u>	ection Report for flood damage work
1.Name of PIUs- R	UD forbesgaij
2.Name of Block/Road-	Forbesgay
A.For Road	Kusmana to halla.
 Damage Location/Chair Damage Lengh Nature of Damage Details of Restoration Material being used i Equipment/Tools bei Procedure taken up in Restored Length 	: 13m + 30m + 106m = 149m : Flood damage diter up 3.5mdepm n Restoration : Local Sand, Blanks and Darber pileter
B. For Bridge 1. Damage Location/Chain 2. Damage Lengh 3. Nature of Damage 4. Details of Restoration i Material being used if if Equipment/Tools bein if Procedure taken up in iv Restored Length	age: : : : : : : : : : : : : : : : : : :

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

KUSMAHA TO HALLA

Block: FORBESGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishangan]

COST OF 1ST CUTTING RESTORATION

Rs 226157.00

COST OF 2ND CUTTING RESTORATION

Rs 784103.00

COST OF 3RD CUTTING RESTORATION

Rs 2908702.00

TOTAL COST OF RESTORATION

Rs

3918962.00

Say

Rs

3918962.00

1201 p/ 2020

(4)11 2 DE

E.E. MIPO

Rechmically Approved for Rs: 39,18,962.00 (Rupees thirty nine lass eighteen thousand Nine hundred sinely two by)

Superintending Engineer Rural Works Department Works Circle, Kishanganj

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM KUSMAHA TO HALLA CUTTING-1

Block: FORBESGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete Job as per specification & direction of Engineer-In-charge,				
		Cum	131.08	627.77	82290.39
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
	CORPUS CONTROL	Mtr.	162,00	75.86	12289.09
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	81.00	40.06	3244.91
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.		02.00	40.00	3244.91
		Each	2185.12	37,35	81606.90
	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.			27.120	0200,50

		Cum	12.15	1870.43	22725.76
	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				
	ADD 12.00 %GST=				
	SAY TOTAL AMOUNT =				226416.00

RWD WORKS

DIV. FORBESGANJ υ-24)**/ AE

RWD WORKS DIV. FORBESGANJ

RWD WORKS
DIV. FORBESGANJ