

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:-

RESTORATION OF ROAD FROM SAIFGANJ TO  
ADIWASI DHATTA TOLA

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

FORBESGANJ

ESTIMATED COST

3443563.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- R.W.D. Forbesganj

2. Name of Block/Road- Forbesganj

A. For Road Saifganj to Adiwasi tola

1. Damage Location/Chainage :

2. Damage Length :  $42m + 24m + 35m = 106m$

3. Nature of Damage : Flood Damage

4. Details of Restoration :

i Material being used in Restoration

: Local sand, B/Bags of Bamba Pile.

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: Filling all cfs properly in damage area.

iv Restored Length

: 106m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N/A

Signature of JE/AE/EE

Signature

(Name of Inspector)

## Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

**SAIFGANJ TO ADIWASI TOLA**

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION Rs 1259469.00

COST OF 2ND CUTTING RESTORATION Rs 976820.00

COST OF 2ND CUTTING RESTORATION Rs 1207274.00

TOTAL COST OF RESTORATION Rs 3443563.00


Say Rs 3443563.00

  
J.E.

  
A.E.

  
Superintending Engineer

*Technically Approved for Rs. 3443563.00 (Rupees Thirty Four Lacs forty three thousand five hundred sixty three only).*

  
**Superintending Engineer**  
Rural Works Department  
Works Circle, Kishanganj

## Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood In JULY 2019 In ARARIA District

**Name of Road:**

**RESTORATION OF ROAD FROM SAIFGANJ TO ADIWASI DHATTA TOLA CUTTING-1**

**Block:** FORBESGANJ

**District:** ARARIA

**Divison :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	820.17	627.77	514877.31
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	756.00	75.86	57349.10
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	252.00	40.06	10095.26
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	12414.64	37.35	463645.90
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	42.00	1870.43	78558.17
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				1124526.00
	ADD 12.00 %GST=				134943.00
	SAY TOTAL AMOUNT =				1259469.00

JE  
3/11/20

RWD WORKS  
DIV.  
FORBESGANJ

AE  
3/11/20

RWD WORKS DIV. FORBESGANJ

E.E.

RWD WORKS  
DIV. FORBESGANJ

Technically Approved for Rs. 1259469.00 (Rupees Twelve Lacs Fifty Nine thousand four hundred Sixty Nine) only.