



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from Ahiyapur chowk to bhikanpur via shahwajpur and mithanpur chowk road

(FDR PART-A)

Restoration Length :- 0.6km

Block:- mushahari

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 447,700.00

:- PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST 1

Inspection Report for Flood Damage Work

Date

- 1 Name of PUs: EE, RWD, Muradpur Cant-1
2 Name of Block/Road: Mushahani / Aniyapur chowk to Shikharpur via Shekhpur and Orithapur chowk

A For Road

- 1 Damage Location/Chainage: at many places
2 Damage Length: 132.5 Mtr.
3 Nature of Damage: Complete Traffic Block to Breach of Road.
4 Details of Restoration Works-

- i Material being used in Restoration Works: Brick Bat
ii Equipments/Tools being used in Restoration Works: JCB, Tractor, Roller, Manual
iii Procedure Taken up in Restoration Works: Immediate traffic restoration
iv Restored Length: 132.5 mtr

B. For Bridge

- 1 Damage Location/Chainage
2 Damage Length
3 Nature of Damage
4 Details of Restoration Works-

- i Material being used in Restoration Works-
ii Equipments/Tools being used in Restoration Works-
iii Procedure Taken up in Restoration Works-
iv Restored Length

N/A


Signature of JE/ AE/ EE


Signature
(Name of Inspector)

प्रतिवेदन

कार्य का नाम - अद्वितीयपुर चौक से मिसरापुर गाथा सव्वाजुड़ और
मिठनपुर चौक पथ में अप्रत्याशित बाढ़ / अतिवृष्टि 2020 से क्षतिग्रस्त
 कतायात बालू करने हेतु आपातकालीन परम्पति कार्य।

परिपत्र - मसाहरी
 दिनांक - 28/2/21
 प्राक्कलित राशि - ₹ 4,47,700/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 4,47,700/- है अद्वितीयपुर चौक से
मिसरापुर गाथा सव्वाजुड़ और मिठनपुर चौक में कतायात बहाली हेतु आपातकालीन
 निर तैयार किया गया है। मिठनपुर चौक
 अनियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.02
 दिने गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में भरकर
 करने का प्रावधान किया गया है। प्राक्कलन वर्तमान बलू अनुसूचित दर पर तैयार किया गया
 महंगांतर स्वीकृति अर्पित है।

Sanjiv Kumar
12/2/2021
 कमीय अनियंता

Sanjiv Kumar
12/2/2021
 सहायक अनियंता

Sanjiv Kumar
15/2/21
 कार्यपालक अति
 ग्रामीण कार्य वि
 कार्य प्रमंडल
 पृष्ठी-1

NAME OF WORK:- Restoration work of Road from Ahiyapur chowk to bhikanpur via shahwajpur and mithanpur chowk road

Total Length :-

3.38

Restoration Length :- 0.6km

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dumping, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	213.19	377,048.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	-	-
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	-	-
	Total Amount			Rs.	377,048.00
	Add for GST @ 12%			Rs.	45,246.00
	Add for Labour Cess @ 1%			Rs.	3,770.00
	Add for Seigniorage Fee			Rs.	21,681.00
	Gross Total Amount			Rs.	447,745.00
	Say			Rs.	447,700.00

[Signature]
12/12/20
J.E.

[Signature]
12/12/20
A.E.
RWD, Sub-Division, Sakra
Mushaharzi

[Signature]
15-12-20
Executive Engineer
RWD(W) Div. Muzaffarpur East 1

Technically approved for 447700=00 (Rs. Four lacs forty seven thousand seven hundred) only,

[Signature]
28-12-20
S.E., RWD
Woods Circle, Muzaffarpur