



बिहार सरकार

## GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from  
jamalabad jp chowk to nawada village

(FDR PART-A)

Restoration Length :- 0.7 km

Block:- mushahari

### DETAILED PROJECT REPORT

UNDER FDR (2245)

### ESTIMATED COST

Rs. 1,263,900.00

:- PREPARED BY :-  
**EXECUTIVE ENGINEER**  
R.W.D. (W) DIVISION  
MUZAFFARPUR EAST 1

## प्रतिवेदन

कार्य का नाम जमासाबाद JP चौक टो नवादा मंजिल

पथ में अप्रत्याशित बाढ़/अतिवृष्टि 2020 से क्षतिग्रस्त पथ में  
कामायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रखण्ड मुजफ्फर  
वित्तीय वर्ष - 2020-2021  
प्रवर्कलित राशि - Rs. 1263900/-

प्रस्तुत प्रावकलन जिसकी प्रवर्कलित राशि 1263900/- है, जमासाबाद JP चौक  
टो नवादा मंजिल प्रखण्ड मुजफ्फर में कामायात बहाली हेतु आपातकालीन मरम्मत के  
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा  
दिए गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में मरम्मत कार्य चालू  
करने का प्रावधान किया गया है। प्रावकलन वर्तमान चालू अनुसूचित दर पर तैयार किया गया है। इसके  
तत्पश्चात् स्वीकृति अपेक्षित है।

Kumil Kumar  
12/12/2020  
कनिष्ठ अभियंता

12/12/20  
सहायक अभियंता,

15.12.20  
कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल मुजफ्फर  
पूर्व-1

## Inspection Report for Flood Damage Work

Date

- 1 Name of PIUs- F.E. (R.D.) Muzaffarpur Ghat-1
- 2 Name of Block/Road- Mushani/ Restoration work of road from Jamalabad JP Chowk to Nivada Village.

A For Road

- 1 Damage Location/Chainage At every Places
- 2 Damage Length 133 mtr.
- 3 Nature of Damage- Complete traffic Block due to Breaching of Road.
- 4 Details of Restoration Works-
  - i Material being used in Restoration Works- Brick Bat, empty cement bag local sand, Bamboo Piling
  - ii Equipments/Tools being used in Restoration Works- Road Roller, Tractor JCB, Mermal
  - iii Procedure Taken up in Restoration Works- Immediate to the Restoration
  - iv Restored Length 133 mtr.

B. For Bridge

- 1 Damage Location/Chainage
- 2 Damage Length
- 3 Nature of Damage
- 4 Details of Restoration Works-
  - i Material being used in Restoration Works-
  - ii Equipments/Tools being used in Restoration Works-
  - iii Procedure Taken up in Restoration Works-
  - iv Restored Length

N/A

*Signature*  
12/12/2020  
Signature of JE/ AE/ EE

*Signature*  
11/12/2020  
Signature  
(Name of Inspector)

**NAME OF WORK:- Restoration work of Road from jamalabad jp chowk to nawada village**

Total Length :- 0.8 km

Restoration Length :- 0.5km

**ABSTRACT OF COST**

Sl. No.		Unit	Rates	Quantity	Amount
1	<b>Providing and Laying of Brick Bats:</b> Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return trip	Cum	1,768.60	498.54	881,718.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	2,415.50	119,326.00
3	providing, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every verticle pile with 150 mm long nails or 38 swg G. I. wire including cost of G.I. or nails complete job as per specification and direction of E/I	Rm	26.40	1,232.50	32,538.00
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	900.00	32,580.00
	<b>Total Amount</b>			<b>Rs.</b>	<b>1,066,162.00</b>
	Add for GST @ 12%			Rs.	127,939.00
	Add for Labour Cess @ 1%			Rs.	10,662.00
	Add for Seignoirage Fee			Rs.	59,158.00
	<b>Gross Total Amount</b>			<b>Rs.</b>	<b>1,263,921.00</b>
	Say			<b>Rs.</b>	<b>1,263,900.00</b>

*[Signature]*  
12/12/20  
J.E.

*[Signature]*  
12/12/20  
A.E.  
RWD, Sub-Division, Salra,  
Mushahar

*[Signature]*  
15-12-20  
Executive Engineer  
RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs. 1263900 = (Rs. Twelve lacs sixty three thousand nine hundred) only.

*[Signature]*  
12-12-20  
S E (RWD)  
Wones chole, Muzaffarpur