



GOVERNMENT OF BIHAR

NAME OF WORK :- Restoration work of Road from chakna
moti babu ke ghar se turki saraiya path tulsi chowk

(FDR PART-A)

Restoration Length :- .3 km

Block:- saraiya

DETAILED PROJECT REPORT

UNDER FDR (2245)

ESTIMATED COST

Rs. 058,600.00

-: PREPARED BY :-
EXECUTIVE ENGINEER
R.W.D. (W) DIVISION
MUZAFFARPUR EAST I

Inspection Report for Flood Damage Work

Date

1 Name of P.U. - C.E. RUD Muradpur Ganga-1
2 Name of Block/Road - Saraiya / Restoration work of road from
Chaleng road baby ke chor se tukhi Saraiya path
Tulsi chowk.

A For Road

1 Damage Location/Chainage At many places

2 Damage Length 51.00 mtr

3 Nature of Damage Complete breach due to breach
of road

4 Details of Restoration Works-

i Material being used in Restoration Works Bricks Bat, Local Sand
Bambhooli Uy.

ii Equipments/Tools being used in Restoration Works- Road, Roller, Tractor
JCB, Magma

iii Procedure Taken up in Restoration Works- Immediate to the
Restoration.

iv Restored Length 51.00 mtr

B. For Bridge

1 Damage Location/Chainage

2 Damage Length

3 Nature of Damage

4 Details of Restoration Works-

i Material being used in Restoration Works-

ii Equipments/Tools being used in Restoration Works-

iii Procedure Taken up in Restoration Works-

iv Restored Length

N/A

Signature of JE/ AE/ EE

Signature

(Name of Inspector)

प्रतिवेदन

कार्य का नाम

चक्रा भीरी बाबू के घर से दुर्गी संस्था पथ

दुलसी चौक

पथ में अप्रत्याशित बाढ़ / अतिवृष्टि 2020 से क्षतिग्रस्त पथ में
यातायात चालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रस्ताव
वित्तीय वर्ष

संस्था

2020-21

प्राक्कलित राशि - Rs

58600/-

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि

58600/-

है.

चक्रा भीरी बाबू

के घर से दुर्गी संस्था पथ प्रखंड - संस्था में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 2521 दिनांक 05.08.2020 द्वारा
दिये गये निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में भरकर पथ को चालू

करने का प्रावधान किया गया है। प्राक्कलन वर्तमान चलू अनुसूचित दर पर तैयार किया गया है। इसकी
वटनांतर स्वीकृति अपेक्षित है।

कनिष्ठ अभियंता

सहायक अभियंता,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल मुजफ्फर
पुरी-1

NAME OF WORK:- Restoration work of Road from chakna moti babu ke ghar se turki saraiya path tulsu chowk

Total Length :-

3.50

Restoration Length :- 0.36

ABSTRACT OF COST

Sl. No.		Unit	Rates	Quantity	Amount
1	Providing and Laying of Brick Bats: Placing tractor at loading point loading with front end loader dumpong, turning for return trip exluding time for haulage and return tirp	Cum	1,768.60	27.91	49,362.00
2	Providing, cutting and fixing of 62 mm to 75 mm dia bamboo piles in size with making shoes and driving etc. complete job as per specification and direction E/I.	Rm	49.40	-	-
3	Providing including labour for filling empty cement bag with local sand, stiching the bag and placing including supply of sutali etc. all complete as per approved design, specification and direction of E/I	Nos	36.20	-	-
Total Amount				Rs.	49,362.00
Add for GST @ 12%				Rs.	5,923.00
Add for Labour Cess @ 1%				Rs.	494.00
Add for Seigniorage Fee				Rs.	2,838.00
Gross Total Amount				Rs.	58,617.00
Say				Rs.	58,600.00

Chintan
J.E. 12/12/2020

12/12/2020
A.E.
RWD, Sub-Division, Saraiya

12/12/2020
Executive Engineer
RWD(W) Div. Muzaffarpur East 1

Technically approved for Rs. 58600-00 (Rs Fifty eight thousand six hundred) only

12/12/2020
SE, RWD
Muzaffarpur