

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:-

RESTORATION OF ROAD FROM PIPRA TO  
JHAKHORAN

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

FORBESGANJ

ESTIMATED COST

1315828.00

Inspection Report for flood damage work

Date:

1. Name of PIUs-

R.M.D. Forbesganj

2. Name of Block/Road-

Forbesganj/Pitua to Shahmoran

**A. For Road**

1. Damage Location/Chainage :

2. Damage Length : - (25.00m)

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration - 1/ Sand, E.C bag, bamboo piles, sunnars, b/ barks

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

- All filling works properly in damage Area  
: 25m

**B. For Bridge**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

N.A

Signature of JE/EE

Signature

(Name of Inspector)

Abstract of Cost

Work- Estimate of Repairing/ Restoration / Making Motorable Roads Damaged during flood in JL  
in ARARIA District

Name of Road:- RESTORATION OF ROAD FROM PIPRA TO JHOKHARAN

Block: FORBESGANJ

DISTRICT: ARARIA

Division: RWD, Works Division, Forbesganj

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION

Rs 720728.00

COST OF 2ND CUTTING RESTORATION

Rs 595566.00

TOTAL COST OF RESTORATION

Rs 1316294.00

  
AE

  
AE

  
EE

Technically approved for Rs 13,16,294 = 13 (Rupees -  
thirteen Lacs Sixteen thousand two hundred and  
Ninty Four) only

S.E.  
Superintending Engineer  
RWD (W) Circle, Kishanganj  
Kishanganj.

## Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood in JULY 2019 in ARARIA District

**Name of Road:**

### RESTORATION OF ROAD FROM PIPRA TO JHAKHORAN CUTTING-1

**Block:** FORBESGANJ

**District:** ARARIA

**Division :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	477.50	627.77	299760.92
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	327.00	75.86	24805.76
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	132.00	40.06	5288.00
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	6294.90	37.35	235093.82
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				