प्रमंडल का नामः ग्रामीण कार्य विभाग, कार्य प्रमंडल सोनपुर

कार्य का नामः– सारण जिला अन्तगर्त दरियापुर प्रखंड में दिघवारा भेल्दी पथ से डेरनी हरिजनटोला ग्रामीण रोड तक बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्नःस्थापन कार्य।

पथ की कुल लम्बाईः– 1.45कि0मी0

क्षतिग्रस्त पथ की लम्बाईः– 157.5मी0

प्राक्कलित राशिः–4.10 लाख

प्रतिवेदन

यह प्राक्कलन सारण जिला अन्तगर्त दरियापुर प्रखंड में दिघवारा भेल्दी पथ से डेरनी हरिजनटोला ग्रामीण रोड तक का बाढ़ से क्षतिग्रस्त (FDR) पथांश का पूर्नःस्थापन कार्य का प्राक्कलन का तैयार किया गया । पथ में CH- 305मी0 से CH-325मी0, एवं CH-900मी0 से CH 938 मी0 में बाढ़ के पानी का अधिक Current रहने के कारण पथ मे भारी कटाव हुआ हैं,जिसके के कारण आवागमन बाधित है।

प्रस्तावित प्राक्कलन में पथ के कटे हुए पथांश में Brick Bats से भरकर पथ को मोटरेबुल करने का प्रावधान किया गया है।

यह प्राक्कलन वर्तमान अनुसूचित दर पर तैयार किया गया है, जिसकी स्वीकृति आपेक्षित हैं।

कनीय अभियंता ग्रामीण कार्य विभाग कार्य प्रशााखा दरियापुर	सहायक अभियंता ग्रामीण कार्य विभाग कार्य अवर प्रंमडल दरियापुर	कार्यपालक अभियंता ग्रामीण कार्य विभाग कार्य प्रमंडल, सोनपुर

Scanned with CamScanner

Inspection Report for flood damage work

Date:

1.Name of PIUs- R-W-D(W) Div Sonitpur

2.Name of Block/Road- Daryaghat, Dighiwara Bhekeli road to Deori Harijan tola Village road

A.For Road

1.Damage Location/Chainage : CH-305-CH-32500, CH-90000-CH93800
2. Damage Lengh : 157.000
3.Nature of Damage : Damaged of Shoulder, and road embankment surface (Partially)
4.Details of Restoration :
i Material being used in Restoration : Bricks bats,
ii Equipment/Tools being used in Restoration works: Spade
iii Procedure taken up in Restoration works : Filling of bricks bats and earth
iv Restored Length : 157.000

B. For Bridge

1.Damage Location/Chainage :
2. Damage Lengh :
3.Nature of Damage :
4.Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works:
iii Procedure taken up in Restoration works :
iv Restored Length :

Signature of JE/AE/EE

8/12/20 J.E Daryaghat

08.12.20 AE

08/12/2020

Signature

(Name of Inspector)

Scanned with CamScanner

Restoration work of road from Dighwara Bheldi road to Derni Harijan tola village road

Length of road-	1.45 km

ABSTRACT OF COST

1	Cpost of Emergent repair of road & Bridge	Rs. 362,828.82
2	Add 1% Labour Cess	Rs. 3,628.29
3	Add 12% GST	Rs. 43,539.46
	Total	Rs. 409,996.57
	Say	Rs. 4.1000

Rs. 4.10 Lakh

Junior Engineer
RWD(W) Dariyapur

08.12.20
Assistant Engineer
RWD(W) sub division Dariyapur

Executive Engineer
RWD(W) DiV
Sonpur

T/A Approved for Rs- 4.10 Lakh (Rupees four lich ten thousand only)

S.E RWD
Chapra

Scanned with CamScanner