

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM MILL CHOWK TO R.T.
MOHAN

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

2184476.00

Inspection Report for flood damage work

Date:

1. Name of PIUs - E.E. R.W.D. Forbesgan

2. Name of Block/Road - Forbesgan/mill chowk to R.T. mohan

A. For Road

1. Damage Location/Chainage :

2. Damage Length : $(95m + 25m) = 70m$

3. Nature of Damage : Flood damage depth = 3m

4. Details of Restoration :

i Material being used in Restoration - 1/2 sand, Bamboo plug, E.C bag, B/b

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: - Filling with proportion in damage
: order.
: 70m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

} N.A

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

MILL CHOWK TO R.T. MOHAN

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION

Rs

924496.00

COST OF 2ND CUTTING RESTORATION

Rs

1259980.00

TOTAL COST OF RESTORATION


Rs

2184476.00

Say

Rs

2184476.00


J.E.


A.E.


E.E.

Technically Approved for Rs. 2184476.00 (Rupees twenty one
lacs eighty four thousand four hundred seventy six) only.


Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM MILL CHOWK TO R.T. MOHAN

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ


Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	707.33	627.77	444043.75
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	600.00	75.86	45515.16
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	300.00	40.06	12018.17
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	5697.49	37.35	212782.44
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	45.00	1870.43	84169.47
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	5.00	5382.71	26913.54
	TOTAL AMOUNT =				825443.00
	ADD 12.00 %GST=				99053.00
	SAY TOTAL AMOUNT =				924496.00


J. S. M. 20

RWD WORKS
DIV.
FORBESGANJ


AE

RWD WORKS DIV. FORBESGANJ


E. S. M. 20

RWD WORKS
DIV. FORBESGANJ