

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

RESTORATION OF ROAD FROM NH-57 COLLEGE  
NAME OF ROAD:- CHOWK BAJRANGBALI CHOWK TO PRABHAKAR LAL  
DAS HOUSE

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

### ESTIMATED COST

2272819.00

Inspection Report for flood damage work

Date:

1. Name of PIUs-

A.M.D Forbesgan

2. Name of Block/Road-

Forbesgan / NH 57 collage chowk Baraangmal  
chowk to Paabhaton Jal Day house.

**A. For Road**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

40m + 35m + 35m = 110m

Flood damage depth = 3.6m

1/ Sand, bamboo mesh runner, E-c bags, B/bags

Empty all pits properly in damuk  
Ann  
110m

**B. For Bridge**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A

Signature of IC/AE/EE

Signature

(Name of Inspector)

## Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

RESTORATION OF ROAD FROM NH-57 COLLEGE CHOWK BAJRANGBALI CHOWK  
TO PRABHAKAR LAL DAS HOUSE

Name of Road:-

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION

Rs 1970425.00

COST OF 2ND CUTTING RESTORATION

Rs 302394.00

TOTAL COST OF RESTORATION

Rs 2272819.00

Say Rs 2272819.00


  
J.E.

  
A.E.

  
E.E.

Technically approved for Rs. 22,72,819.00 (Twenty two Lacs  
Seventy two thousand eight hundred nineteen Only)

**Superintending Engineer**  
Rural Works Department  
Works Circle, Kishanganj

  
**Superintending Engineer**  
Rural Works Department  
Works Circle, Kishanganj

## Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood in JULY 2020 in ARARIA District

**Name of Road:**

**RESTORATION OF ROAD FROM NH-57 COLLEGE CHOWK BAJRANGBALI CHOWK TO PRABHAKAR LAL  
DAS HOUSE CUTTING-1**

**Block:** FORBESGANJ

**District:** ARARIA

**Division :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1040.39	627.77	653126.56
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	900.00	75.86	68272.74
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	450.00	40.06	18027.26
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	19811.72	37.35	739902.57
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	42.19	1851.91	78127.60
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	37.50	5382.71	201851.53
	TOTAL AMOUNT =				1759308.00
	ADD 12.00 %GST=				211117.00
	SAY TOTAL AMOUNT =				1970425.00

*[Signature]*  
JE  
07/11/20

RWD WORKS  
DIV.  
FORBESGANJ

*[Signature]*  
AE  
6/11/2020

RWD WORKS DIV. FORBESGANJ

E.E.

RWD WORKS  
DIV. FORBESGANJ