

# RURAL WORKS DEPARTMENT



## GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM KHAIRKHA TO  
YADAV TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

### ESTIMATED COST

5284633.00

Inspection Report for flood damage work

Date:

1. Name of PIUs- E.E. R.W.D. Forbeggan

2. Name of Block/Road- Forbeggan / Khairtha to Yadav Tola

**A. For Road**

1. Damage Location/Chainage :

2. Damage Length : 62.10 m

3. Nature of Damage : - Flood damage depth = 2 m

4. Details of Restoration :

i Material being used in Restoration - 2/ sand, B/bent, E-c bag, Bamboo piles, runners

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: Repair all cuts properly in damage area  
: 62 m

**B. For Bridge**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A

Signature of JE/AE/EE



Signature

(Name of Inspector)

## Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2020 in ARARIA District

Name of Road:-

KHAIRKHA TO YADAV TOLA

Block: FORBESGANI

District: ARARIA

Division : RWD, Works Division, FORBESGANI


Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION	Rs	2449615.00
COST OF 2ND CUTTING RESTORATION	Rs	1232147.00
COST OF 3RD CUTTING RESTORATION	Rs	903517.00
COST OF 4TH CUTTING RESTORATION	Rs	699354.00

TOTAL COST OF RESTORATION Rs 5284633.00


Say Rs 5284633.00

  
J.E.

  
A.E.

  
E.E.

Technically Approved for Rs. 5284633.00 (Rupees Fifty two  
lacs Eighty four thousand Six hundred thirty three) only.

  
Superintending Engineer  
Rural Works Department  
Works Circle, Kishanganj

## Abstract of Cost

**Name of Work :** Estimate for Repairing/Restoration/Making Motorable Roads  
Damaged during flood in JULY 2020 In ARARIA District

**Name of Road:**

### RESTORATION OF ROAD FROM KHAIRKHA TO YADAV TOLA CUTTING-1

**Block:** FORBESGANJ

**District:** ARARIA

**Divison :** RWD, Works Division, FORBESGANJ

**Circle:** RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1707.07	627.77	1071647.90
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	1488.00	75.86	112877.60
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	372.00	40.06	14902.53
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	18946.73	37.35	707598.33
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.	Cum	41.85	1870.43	78277.61
		meter	37.50	5382.71	201851.53
	TOTAL AMOUNT =				2187156.00
	ADD 12.00 %GST=				262459.00
	SAY TOTAL AMOUNT =				2449615.00

  
 JE  
 RWD WORKS  
 DIV.  
 FORBESGANJ

  
 AE  
 RWD WORKS DIV. FORBESGANJ

E.E.  
 RWD WORKS  
 DIV. FORBESGANJ