

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM BHAGKOHALIA TO
MANDAL TOLA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

1644069.00

Inspection Report for flood damage work

Date:

1. Name of PIUs-

R.W.D. Forbesganj

2. Name of Block/Road-

Forbesganj

A. For Road

Bag Bhagkohalia to Mandal tola

1. Damage Location/Chainage :

2. Damage Length : 80.0m

3. Nature of Damage : Flood damage with

4. Details of Restoration :

i Material being used in Restoration

: Local sand, B/ds & bamboo pile etc

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

: filling all cut properly

iv Restored Length

: 80.0m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N.A

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM BHAGKOHALLA TO MANDAL TOLA

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	891.67	627.77	559762.97
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	960.00	75.86	72824.26
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	480.00	40.06	19229.08
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	18246.08	37.35	681431.37
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	72.00	1870.43	134671.16
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				1467919.00
	ADD 12.00 %GST=				176150.00
	SAY TOTAL AMOUNT =				1644069.00


JE
RWD WORKS
DIV.
FORBESGANJ


AE
RWD WORKS DIV. FORBESGANJ


E.E.
RWD WORKS
DIV. FORBESGANJ

Technically Approved for Rs. 1644069.00 (Rupees sixteen
lacs forty-four thousand sixty nine) only.


Superintending Engineer
Rural Works Department
Works Circle, Kishanganj