

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM MANIKPUR TO RAHIK
PATHRA MORE

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

9861880.00

Inspection Report for flood damage work

Date:

1. Name of PIUs-

E.E.A.M.D Forbelgari

2. Name of Block/Road- Forbelgari / mampura to Bahik Pathra more "

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 74m + 80m + 100m + 50m + 45m + 40m + 30m = 419m

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration - 1/ Sand, bamboo piling, sunner, E.C bag, b/bat

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

- Fixing All culs properly in dense area
:- 419 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length



Signature of JE/AE/EE





(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

MANIKPUR TO RAHIK PATHRA MORE

Name of Road:-

District: ARARIA

Block: FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Division : RWD, Works Division, FORBESGANJ

COST OF 1ST CUTTING RESTORATION

Rs 1598860.00 ✓

COST OF 2ND CUTTING RESTORATION

Rs 1924136.00 ✓

COST OF 3RD CUTTING RESTORATION

Rs 2286085.00 ✓

COST OF 4TH CUTTING RESTORATION

Rs 2328683.00 ✓

COST OF 5TH CUTTING RESTORATION

Rs 1724116.00 ✓

TOTAL COST OF RESTORATION

Rs 9861880.00 ✓

Say Rs 9861880.00

[Signature]
5/11/2020
S.E.

[Signature]
5/11/2020
A.C.

[Signature]
5/11/20

Technically Approved for Rs. 9861880.00 (Rupees Ninety Eight Lacs Sixty one thousand Eight hundred Eighty only.)

[Signature]
21/11/20
Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM MANIKPUR TO RAHIK PATHRA MORE CUTTING-1(900M)

Block: FORBESGANJ


District: ARARIA

Divison : RWD, Works Division, FORBESGANJ


Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1140.83	627.77	716182.72
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	750.00	75.86	56893.95
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	300.00	40.06	12018.17
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	13867.02	37.35	517887.84
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	66.60	1870.43	124570.82
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				1427554.00
	ADD 12.00 %GST=				171306.00
	SAY TOTAL AMOUNT =				1598860.00


JE
RWD WORKS
DIV.
FORBESGANJ


AE
RWD WORKS DIV. FORBESGANJ


E.E.
RWD WORKS
DIV. FORBESGANJ

Technically Approved for Rs 1598860.00 (Rupees fifteen Lacs Ninety Eight Thousand Eight hundred Sixty only).