

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM NH-57 SIRSIYA
GRIDHAR PATTI VIA PARWAHA GHIWAHA BELSANDI

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

9827397.00

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood In JULY 2020 In ARARIA District

Name of Road:- **RESTORATION OF ROAD FROM NH-57 SIRSIYA GRIDHAR PATTI VIA PARWAHA
GHIWAHA BELSANDI**

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ


Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION	Rs	1273780.00
COST OF 2ND CUTTING RESTORATION	Rs	7580078.00
COST OF 3rd CUTTING RESTORATION	Rs	973539.00

TOTAL COST OF RESTORATION Rs 9827397.00

Say Rs 9827397.00



J.E.


A.E.


E.E.

Technically approved for Rs. 98,27,397 (Rupees ninty eight Laes
twenty seven thousand three hundred ninty seven Only-)

Superintending Engineer
Rural Works Department
Works Circle, Kishanganj


Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Inspection Report for flood damage work

Date:

1. Name of PIUs- RWD Forbesganj

2. Name of Block/Road- Forbesganj

A. For Road NH57 Sirsiya gridhar Patti via Parwah ghlwah belsandi

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration : Flood damage ditch upto 25m depth.

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: Local Sand, Brickbat and Bamboo Piling.
: Filling all cuts properly. See bag etc.
: 207m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

N/A

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 In ARARIA District

Name of Road:

RESTORATION OF ROAD FROM NH-57 SIRSIYA GRIDHAR PATTI VIA PARWAHA GHIWAHA BELSANDI

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1508.00	627.77	946679.51
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	312.00	75.86	23667.88
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	156.00	40.06	6249.45
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	3232.03	37.35	120705.67
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	21.60	1851.91	40001.33
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5054.05	0.00
	TOTAL AMOUNT =				1137304.00
	ADD 12.00 %GST=				136476.00
	SAY TOTAL AMOUNT =				1273780.00


 JE
 RWD WORKS
 DIV.
 FORBESGANJ


 AE
 RWD WORKS DIV. FORBESGANJ


 E.E.
 RWD WORKS
 DIV. FORBESGANJ