



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR

FDR

YEAR 2020-21

Detailed Project Report

Division : Rosera

District :	Samastipur	Block :	Bithan
Name of Road :	<u>Sakhwa to Bhinauli^{kh}</u>		

SUBMITTED BY
THE EXECUTIVE ENGINEER
WORKS DIVISION, ROSERA

FDR

Detailed Estimate for

Sakhwa to Bhinauli^{kh}

Block : Bithan
District : Samastipur

ABSTRACT OF COST FOR ROAD

SI No	Item of Work	Amount (In Rs)	
		As per Estimate	
1	Total Cost for Pavement Works		410328.08
	Total Cost of Project :	Rs -	410328.08
	Total Cost Including (GST + L.Cess) 13% :	Rs -	53342.65
	Total :	Rs -	463670.74
	Say (Lakh) :	Rs -	4.64

Kamran
20/12/20
Junior Engineer

RWD (W) Section, Bithan

Reha
30.12.21
Asstt. Engineer

RWD (W) S. Div. Bithan

Amal
30.12.21
Executive Engineer
RWD (W) Div, Rosera

Technical Copy Approved for Rs 4.64 Lakh say four
Lakh say four thousand only.

Amal
21.1.21
बसोदय बसोदय
बाबोय बाबोय विना
बाबोय बाबोय, बसोदय
19.1.21

FDR

Sakhwa to Bhinauli

District : Samastipur

Block : Bithan

Total Length (Km): 0.60

Sl No	Reference To Mord Spec.	Brief Description of Item	No	Measurements			Unit	Quantity	Rate (Rs)	Amount (Rs)
				L (m)	B (m)	D (m)				
1	401	Supply filling brick bat compacted manually	2	20.00	1.37	0.30	cum	16.44		
			3	20.00	1.50	0.40	cum	36.00		
			5	15.00	2.50	0.20	cum	37.50		
			3	20.00	1.50	0.40	cum	36.00		
			3	30.00	3.75	0.16	cum	54.00		
			2	20.00	1.50	0.40	cum	24.00		
			4	26.00	1.55	0.25	cum	40.30		
		Total Quantity :					cum	244.24	1680.02	410328.08
		Total Cost of Pavement in Rs :								4.10

[Signature]
30/12/20
Junior Engineer
RWD (W) Section, Bithan

[Signature]
30.12.20
Asst. Engineer
RWD (W) S. Div. Bithan

[Signature]
30.12.20
Executive Engineer
RWD (W) Div, Rosera

प्रतिवेदन


योजना का नाम :

Sakhwa to Bhinauli


प्रस्तावित प्राक्कलन ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक-2789 दिनांक-21/08/2020 एवं समस्तीपुर जिलाधिकारी, समस्तीपुर के आदेश के अनुपालन के अलोक में में कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसड़ा के निदेशन में तैयार किया गया है। यह पथ विगत बाढ़ में डूबने एवं पानी के Over Lapping होने के कारण काफी क्षतिग्रस्त हो चुका है। इस पथ में क्षतिग्रस्त मर्दों का आवश्यकतानुसार दिनांक-1/7/20 से प्रभावी वर्तमान अनुसूचित दर पर प्रावधान किया गया है, जो जनहित में आवश्यक है। प्राक्कलन आवश्यक कार्यवाई हेतु समर्पित।


20/12/20

कनीय अभियंता
ग्रामीण कार्य विभाग
नर्य प्रशाखा, Bitthan


20/12-20

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल- Bitthan


20/12/20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल-रोसड़ा

ANALYSIS of RATES. BRICK BAT Filling.

1. ~~Granular sub~~ providing brick bats including spreading, laying and picking with C.I. Hammer in layers not exceeding 75MM thick including cost of eight barriers, dangles, signal, chokidar, taxes, Royalty, etc, and complete job, as per specifications and directions of S/O including cost of bricks. - - - all complete job.

Unit - cum.

assuming - 2.892 M³

Cost of Brick bats - 2.892 M³ @ 1096 = 00 - Rs 3169 = 87
 Maxdara unskilled Local Lab 0.692 M³ @ 141 = 95/M³ Rs 89 = 65

Labour (unskilled)

1. Carrying, spreading, carrying and picking unskilled labour 1.5 NO @ 287 = 00 - Rs 430 = 50
 Compaction of brick bats with C.I. Hammer, 0.670 NO @ 287 = 00 - Rs 192 = 29.
 Over Head Charge @ 6% on (a+b) Total = 4045 = 29

Rate/M³ - Rs 1428 = 42/M³.

Carriage Cost

Carriage for Bricks (1 M³ bat) for 500 NO @ 669 = 50/M³ - Rs 199 = 86
 Local sand 0.320 M³ @ 97 = 00/M³ - Rs 21 = 34.
 Total Rs 1648 = 81.
 31 = 24
 Total 1680 = 02

2. Granular sub. base, with well Graded Material, Take up by Mix and Place Method, for grading II Material and complete job.

Labour - Note - 0.48 NO @ 305 = 00 - Rs 146 = 40
 70% dars skilled - 2.0 NO @ 364 = 00 - Rs 728 = 00
 Maxdara unskilled - 10.0 NO @ 287 = 00 - Rs 2870 = 00
 Material - 300.0 M³

Tractor Manual Grader 6.0 hour @ 573 = 20 Rs 3439 = 20
 Three wheel 80-100 KN 30.0 hour @ 803 = 00/hour - Rs 24090 = 00
 10 M³/hour
 Tractor with vibrator 12.0 hour @ 573 = 20 - Rs 6878 = 40
 25 M³/hour
 Water Tanker 6K capacity 5.0 hour @ 184 = 00 - Rs 920 = 00
 Total 39072 = 00

Material

Course Graded Granular sub base
 53MM to 9.5MM, 95% - 134.40 M³ @ 604 = 91/M³ - Rs 80695 = 00
 9.5MM to 2.36MM 25% 96.00 M³ @ 514 = 58/M³ - Rs 49410 = 00
 2.36MM below Local sand 153.60 M³ @ 141 = 85/M³ Rs 21788 = 00
 make 30 KRD @ 40 = 00/M³ - Rs 1200 = 00
 Total - 1,92,155 = 00
 11529 = 00
 Add over Head Charge 6% Total - 2,04,084 = 00

4. 5th Street Gravel II - 4.7118' - $\frac{8.00}{4.99} \times 6.83 \times 1.0 \times 1.0 = 11.12$
 5th Street Gravel II - 4.7118' - $\frac{8.00}{4.99} \times 6.83 \times 1.0 \times 1.0 = 11.12$

B. Gravel II + 6.50' $\frac{8.00}{4.99} \times 7.60 \times 1.0 \times 1.0 = 12.21$
 6.50' $\frac{8.00}{4.99} \times 7.60 \times 1.0 \times 1.0 = 12.21$

C. Local Sand 4.7118' - $\frac{8.00}{6.00} \times 7.60 \times 2.0 \times 1.0 = 25.27$
 4.7118' - $\frac{8.00}{6.00} \times 7.60 \times 2.0 \times 1.0 = 25.27$

D. 1st Street - $\frac{8.00}{2.00} \times 6.83 \times 7.0 \times 1.0 = 19.12$
 1st Street - $\frac{8.00}{2.00} \times 6.83 \times 7.0 \times 1.0 = 19.12$

E. 1st Street - $\frac{8.00}{6.00} \times 7.60 \times 1.0 \times 1.0 = 1.27$
 1st Street - $\frac{8.00}{6.00} \times 7.60 \times 1.0 \times 1.0 = 1.27$

F. 5th Street (mix gravel) - $\frac{8.00}{4.99} \times 6.83 \times 1.0 + 0 = 11.12$
 5th Street (mix gravel) - $\frac{8.00}{4.99} \times 6.83 \times 1.0 + 0 = 11.12$

G. 5th Street (mix gravel) - $\frac{8.00}{4.99} \times 6.83 \times 1.0 + 0 = 11.12$
 5th Street (mix gravel) - $\frac{8.00}{4.99} \times 6.83 \times 1.0 + 0 = 11.12$

H. 5th Street (mix gravel) - $\frac{8.00}{4.99} \times 6.83 \times 1.0 + 0 = 11.12$
 5th Street (mix gravel) - $\frac{8.00}{4.99} \times 6.83 \times 1.0 + 0 = 11.12$

I. 5th Street (mix gravel) - $\frac{8.00}{4.99} \times 6.83 \times 1.0 + 0 = 11.12$
 5th Street (mix gravel) - $\frac{8.00}{4.99} \times 6.83 \times 1.0 + 0 = 11.12$

कार्यपालक अभियंता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, समस्तीपुर।

पत्रांक..... ५५०१ रोसड़ा

दिनांक 24.12.20

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, समस्तीपुर।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, रोसड़ा।

विषय:- FDR अन्तर्गत पथों को जाँच करने के संबंध में।


प्रसंग:- आपका पत्रांक 23.12 दिनांक 22.12.20

महाशय,

उपर्युक्त प्रासंगिक विषयक के संबंध में कहना है कि आपके द्वारा निम्न पथों की सूची जाँच करने हेतु समर्पित किया गया था। पथों की जाँच की गई एवं जाँचोपरान्त सभी पथ पूर्ण पाया गया। प्रतिवेदन के साथ आवश्यक कार्रवाई हेतु समर्पित।

अनु०:- यथोक्त।

विश्वासभाजन


24.12.20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, समस्तीपुर।

ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसड़ा अंतर्गत FDR के तहत मरम्मत कराए गए पथों की सूची एवं जांच से संबंधित प्रतिवेदन

क्रम	प्रखंड	पथ का नाम	कराए गए कार्य	मरम्मत कराए गए पथ की लंबाई	प्राक्कलित राशि	अभ्युक्ति
1	Bithan	Larjhaghat to Darbhanga Jila ke Samaila Path	Brick Bat Filling	2.00	16.80	पूर्ण
2	Bithan	Ramsainia Pool se Warahi Chowk Path	Brick Bat Filling	0.70	8.69	पूर्ण
3	Bithan	Larjha Ghat Pool se chhechni Railway Bandh tak	Brick Bat Filling	2.00	8.90	पूर्ण
4	Bithan	Sohma to Sukhashan bandh	Brick Bat Filling	0.60	7.95	पूर्ण
5	Bithan	Sakhwa to Bhinauli	Brick Bat Filling	0.60	4.64	पूर्ण
6	Bithan	Construction of Road from Chandouli chpok to Primary Swathya kendra	Brick Bat Filling	1.13	4.68	पूर्ण
7	Bithan	Main road tetrahi to Utkramit Madhya Vidhyalay Tetrahi	Brick Bat Filling	0.25	0.98	पूर्ण
8	Bithan	Narpa main road to Utkramit Madhya Vidyalay Kaurahi	Brick Bat Filling	0.80	7.51	पूर्ण
9	Bithan	Pusho Chowk to pusho	Brick Bat Filling	7.00	7.95	पूर्ण
10	Bithan	Narpa Golambar to Utkramit Madhya Vidyalay Narpa	Brick Bat Filling	0.30	7.81	पूर्ण
11	Bithan	Bhuidhar main Road to Prathmik Vidyalay Bhuidhar	Brick Bat Filling	0.55	5.24	पूर्ण
12	Bithan	Bhan Bhuara main Road to Prathmik Vidyalay Bhan Bhaura	Brick Bat Filling	0.15	1.43	पूर्ण
13	Bithan	Teknwajpur main Road to Prathmik Vidyalay Teknwajpur	Brick Bat Filling	0.30	1.78	पूर्ण
14	Bithan	L023-L022 to Khota tilakpur (TRACK23)	Brick Bat Filling	1.34	11.96	पूर्ण
15	Bithan	Belaun Path se Salokhar path	Brick Bat Filling	0.85	7.95	पूर्ण
16	Bithan	Chardauli - Sihma	Brick Bat Filling	0.96	3.02	पूर्ण
17	Bithan	Manorma bandh to Salha approach	Brick Bat Filling	0.15	5.98	पूर्ण
18	Bithan	Sukhashan bandh se Phuhiya Path	Brick Bat Filling	0.20	9.65	पूर्ण
19	Bithan	Bithan REO road to Karanchi Sirsia	Brick Bat Filling	2.20	7.95	पूर्ण
20	Bithan	Construction of Road from Pusho Saraswati chowk to Beloun Bhaya Barahi Belahi	Brick Bat Filling	0.90	8.91	पूर्ण
21	Bithan	Chandauli to Karanchi	Brick Bat Filling	0.20	3.05	पूर्ण

24/12/20

कार्यपालक अभियंता
ग्रामीण कार्य विभाग, कार्य प्रमंडल-समस्तीपुर