

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI

Name of Raad :- Motarable Work for Booth No 160 in Hayaghat Vidhan Sabha

Length of the Road:- 0.500 KM
Effective Length 0.154 KM.

[Signature]
T.E. Baheri

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	1,17,698.76
2	Add 12 % GST	14,123.85
3	Add Seigniorage	6,698.60
4	Add 1 % Labour Cess	1,176.99
Total cost:-		1,39,698.20

Sum Rs. 1,39,698.20

[Signature]
14.12.2020
Junior Engineer
Baheri

[Signature]
Assistant Engineer
Baheri

[Signature]
Executive Engineer
R.W.D.(W) Division, Darbhanga-1


कार्यालय अभियंता, ग्राहक का दिनांक, कार्यालय - फुलपारा का पत्रांक: 542 अ/30
दिनांक: 07/04/2021 को द्वारा समर्पित जोय प्रतिवेदन को आधार पर -
Post - fees T/A for Rs. 1,39,698.20 (Rupees one lac -
thirty nine thousand six hundred ninety eight) only.

[Signature]
09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021


Detailed estimate for making moterale road.

Name of Raad :- Motarable Work for Booth No 160 in Hayaghat Vidhan Sabha
Block :- BAHERI
District :- DARBHANGA
R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	Length (m)	Breadth (m)	Depth / Height (m)	Quantity	Rate	Amount
1	Labour and placing of brick bats with light raming including cost of brick bats by tractor	Cum	From Booth 160						
			0.000 KM to 1.000 KM						
			1	20.00	2.40	0.200	9.600		
			1	10.00	2.00	0.250	5.000		
			1	18.00	1.80	0.200	6.480		
			1	12.00	1.75	0.250	5.250		
			1	22.00	2.60	0.250	14.300		
			2	5.00	1.80	0.180	3.240		
			1	2.00	1.30	0.200	0.520		
			1	4.00	1.40	0.200	1.120		
			2	5.00	1.75	0.220	3.850		
			1	3.00	1.60	0.200	0.960		
			2	4.60	2.30	0.600	12.696		
					</				


 14.12.2020
 Junior Engineer
 Baheri


 15/12/20
 Assistant Engineer
 Baheri


 Executive Engineer
 R.W.D.(W) Division, Darbhanga-1