

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI


Middle School Mithuniyato

Name of Raad :- Motarable Work for Booth No in 184 & 187 in Hayaghat
Vidhan Sabha

Length of the Road:- 1.000 KM
Effective Length 0.151 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount (in Rs.)
1 Cost for restoration	Qty = 88.981 m ³ @ 1867.76	1,66,194.22
2 Add 12 % GST		19,943.31
3 Add Seigniorage		9,458.63
4 Add 1 % Labour Cess		1,661.94
Total cost:-		1,97,258.09



14.12-2020
Junior Engineer
Baheri


15/12/20
Assistant Engineer
Baheri


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यालय, जिला बाहरी, कार्यालय - लखनऊ का पत्रांक 542 3130
दिनांक 07/04/2021 के द्वारा समर्पित मात्र प्रतिवेदन के माध्यम पर -

Post - dated T/A for Rs. ~~35.50~~ 1,97,258.09 (Rupees one
Lac ninety seven thousand two hundred fifty eight) only.



09.04.21
Superintending Engineer
RWD, Works Circle, Darbhanga
09/04/2021

Detailed estimate for making moterable road.


Motarable Work for Booth No in 184 & 187 in Hayaghat Vidhan Sabha

BAHERI
DARBHANGA
R.W.D. Division Darbhanga-1

Item	Unit	No.	Length (m)	Breadth (m)	Depth / Height (m)	Quantity	Rate	Amount
Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum	From Booth 184 0.000 KM to 1.000 KM						
		1	25.00	2.10	0.200	10.500	✓	
		1	10.00	1.90	0.250	4.750	✓	
		1	18.00	1.80	0.200	6.480	✓	
		1	15.00	1.75	0.250	6.563	✓	
		1	25.00	2.60	0.250	16.250	✓	
		2	3.00	1.80	0.180	1.944	✓	
		1	2.00	1.30	0.200	0.520	✓	
		1	1.80	1.40	0.200	0.504	✓	
		1	3.00	1.30	0.220	0.858	✓	
		1	1.70	1.20	0.200	0.408	✓	
		2	4.60	2.30	1.900	40.204	✓	
					Total	88.981	1867.76	166194
								166194


12.12.2020
Junior Engineer
Baheri


15/12/20
Assistant Engineer
Baheri


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

Total Rs. 1,66,194-00

12/12/20