


Abstract of cost for Restoration work of Sonoul Sultan Barari Jagadish Bazar PWD Path after flood 2020.

Sl. No.	Item of work	Unit	Quantity	Rate	Amount
1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.				
	(a) Bricks bat	cum	499.61	1546.00	772397.00
	(b) Rubbish	cum	124.9	742.00	92676.00
2	S/F/F1000 dia NP3 Hume Pipe ..do..do..E/I.	M	15	3348.6	50229.00
Total					915302.00
Add 1% labour Cess					9153.00
Add 12% GST					109836.00
Grand Total					1034291.00
Say Rs					1034290.00


J.E.


A.E.


E.I.

यह प्रारम्भन आधीक्षण अभियंता कार्य अंचल सीतामढ़ी द्वारा गठित
गौचदल (कार्य प्रालेक अभियंता सीतामढ़ी) के गौच प्रतिवेदन
254/29-1-21

Technically Approved for Rs 1034290 = 00 (Rupees Ten
lakh Thirty four thousand Two hundred Ninety) only.



R.S.E.
R.W.D. (W) Circle
Sitamarhi

Detailed Estimate of Restoration work of Sonoul Sultan Barari Jagadish Bazar PWD Path after flood 2020.

sl no. 1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/l.						
	from chainage in M	to chainage in M	No.	length in M	width in M	depth in M	Quantity in cum
	200	213		13.00	4.00	3.50	182.00
	250	262		12.00	3.80	1.20	54.72
	450	453	2	3.00	3.10	0.40	7.44
	1050	1057		7.00	2.00	2.00	28.00
	1650	1656.5		6.50	3.00	1.80	35.10
	1700	1794		94.00	4.50	0.75	317.25
							624.51
(a)	Brick Bats 80%						499.61
(b)	Local Sand/ Rubbish 20%						124.90
Sl. No. 2	S/F/F1000 dia NP3 Hume Pipe ..do..do..E/l.						
	6x2.50 M						15.00 M

 9-4-21

J.E

 04.02.21

A.E.

 04.02.21