



Abstract of cost for Restoration work of Kataiya to Ashopur Road after flood 2020.

Sl. No.	Item of work	Unit	Quantity	Rate	Amount
1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.				
	(a) Bricks bat	cum	101.52	1546.00	156950.00
	(b) Rubbish	cum	25.38	742.00	18832.00
Total					175782.00
Add 1% labour Cess					1758.00
Add 12% GST					21094.00
Grand Total					198634.00
Say Rs					198630.00


J.E.


A.E.


E.I.

यह प्राकलन अधीक्षण अभियंता कार्य अंचल सीतामढ़ी द्वारा गहिल
अधिदल (कमिषनर अभियंता सीतामढ़ी) के द्वारा प्रसिद्ध
254/29-1-21

Technically Approved for Rs 198630.00 (Rupees One
Lakh Ninety eight thousand Six hundred Thirty) only.


S.E.
R.W.D. (W) Circle
Sitamarhi

Detailed Estimate of Restoration work of road from Kataiya to Ashopur Road after flood 2020

sl no. 1	Supplying & filling of brick bats with manual compactiondo....do all complete job as per direction of E/I.						
	from chainage in M	to chainage in M	length in M	width in M	depth in M		Quantity in CUM
1	98	190	92.00	2.3	0.45		95.22
2			24.00	1.8	0.4		17.28
3	570	602	32.00	1.5	0.3		14.40
							126.90
(a)	Brick Bats 80%						101.52
(b)	Local Sand/ Rubbish 20%						25.38

J.E.

A.E.