

Nagdah to Kapasiya

Name of Road:

Block : BENIPATTI

District: MADHUBANI

Length : 1.950 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)								
		CH-0.600 KM	1	3	2.00	0.60	3.60			
		CH-0.700 KM	1	3.00	3.00	0.60	5.40			
		CH-0.800 KM	1	2.00	2.00	0.30	1.20			
		CH-0.970 KM	1	5.00	4.00	0.60	12.00			
		CH-0.970 KM	1	1.00	1.50	0.60	0.90			
		CH-1.000 KM	1	10.00	2.50	0.60	15.00			
		CH-1.000 KM	1	2.50	3.00	0.60	4.50			
		CH-1.020 KM	1	3.00	5.00	0.30	4.50			
		CH-1.040 KM	1	10.00	3.00	0.90	27.00			
		CH-1.200 KM	1	5.00	2.50	0.90	11.25			
		CH-1.400 KM	2	5.00	3.00	0.90 + 0.6/2	27.00	22.50		
		CH-1.400 KM	1	7.00	3.50	1.20 + 0.6/2	29.40	22.05		
		CH-1.400 KM	2	3.00	2.00	0.90	10.80			
							Total 182.55	CUM	1867.76	284926.79

140.70 M³

Add GST 12% Rs=

34191.21

Add Labour Cess 1% Rs=

2849.27

Total Rs=

321967

Rs (140.70 M³ × 1063 × 10%)

14956

[Signature]
JE

RWD BENIPATTI

[Signature]
AE

RWD BENIPATTI

[Signature]
EE

RWD BENIPATTI

Rs 3,11,913=00

સાધારણ સંચયન, આ નો નો, સંચયન. જેણે આ પત્ર:- 01/05/2021
- 10/05/2021 કે સાર સંચયન. બાદ સંચયન કે સંચયન

Post facto T/A Rs 3,11,913=00 (Rupees -
Three lacs eleven thousand nine hundred thirteen only.)

[Signature]
Superintending Engineer
RWD, Works Circle, Darbhanga