

Name of Road: NH 105 to Paraul

Block : BENIPATTI

District: MADHUBANI

Length : 3.300 KM

No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)								
		Ch 0.050 KM	1	25.00	3.00	0.30	22.50			
		Ch 0.150 KM	1	20.00	3.00	0.30	18.00			
		Ch 0.200 KM	2	5.00	3.00	0.30 ⁺² 7.5	9.00			
		Ch 0.200 KM	2	3.00	3.00	0.30 ⁺² 4.5	5.40			
		Ch 0.300 KM	2	3.00	3.00	0.30	5.40			
		Ch 0.350 KM	1	32.00	3.00	0.60 ⁺² 52.80	57.60			
					110.7 m ³	Total	117.9000	Cum	1867.76	220208.90

Add GST 12% Rs=

26425.07

Add Labour Cess 1% Rs=

2202.09

Total Rs=

248836

206761.00

24811.00

2067.00

11760.00

Sum Rs = 2,45,406.00

[Signature]
JE

RWD BENIPATTI

[Signature]
AE

RWD BENIPATTI

[Signature]
EE

RWD BENIPATTI

कार्यपालक अभियंता का द्वारा यह कि कार्य प्रमाणिक वरीपुर के
प्रमाणिक: 01 कुंभ 3/2024 / दिनांक:- 10.05.2024 / के द्वारा समर्थित

गौरव प्रसिद्ध के आचार्य पर

Post fact to T/A 78, Rs 2,45,460 = 00

Two Lacs twenty five thousand four hundred
sixty rupees only.

[Signature]
13.5.21

Superintending Engineer

RWD, Works Circle, Darbhanga

13/05/2024