

GOVERNMENT OF BIHAR

FDR (2020-21)



Name of Road- Dhaka Pakridayal to Lahan Dhaka	Length-0.600 Km
Estimated Cost- Rs.:- 5,52,500.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- दाका - पकड़ीदमाल से लहन् दाका,

प्रखंड का नाम :- दाका .

पथ की लम्बाई :- 0.600 कि०मी०

शीर्ष :- 3054

प्राक्कलित राशि :- ₹ 552,500.00


अनुरक्षण अवधि :- निर्मिताधीन

प्रस्तुत प्राक्कलन दाका - पकड़ीदमाल से लहन् दाका में अतिवृष्टि / वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो0 552,500.00 रु0 है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि / वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से भरने का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप हैं।


7.9.2020

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाका


07/09/2020


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल, दाका

Estimate for Restoration work of Road from Dhaka Pakridayal to Lahan Dhaka for the year 2020-21 in Dhaka Block.

Length:- 0.600 Km

SL No.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron Including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat)				
	CH:- 300M to 310M 10.00x4.00+4.50/2x0.450 = 19.125M ³				
	CH:- 330M to 340M 10.00x 4.10+4.80/2x0.400 = 17.80M ³				
	CH:-400M to 410M 10.00M x4.00+4.50/2x0.350/2 = 14.875M ³				
	CH:-470M to 490M 20.00x4.10x0.600 = 49.20M ³				
	CH:-510M to 520M 10.00x4.00x0.600 = 24.00M ³				
	CH:-600M to 620M 20.00x4.00x0.450 = 36.00M ³				
	CH:-750M to 795M 45.00x4.00x0.600 = 108.00M ³				
	Total= 269.00M ³	M ³	269.00	2053.84	5,52,483.00
			Total=	Rs.	5,52,483.00
				Say Rs.	5,52,500.00


1.3.2020
JE.


07/09/2020
AE.


07/09/2020
EE.

That For fee T.A. IT/S is accorded for Rs. 5,52,500.00
..... crore Five Fitty Two m.
Five hundred


S.E. (R.W.D.)
works Circle
Motihari
25-12-20

Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Dhaka - Pakriddyal to Lahan Dhaka

(A) For Road


1. Damage Location Chainage:-

2. Damage Length:- 125 m

3. Name of Damage:- Road damaged due to Flood.

4. Details of Restoration Work:-

- (i) Material being used in Restoration works:- Bricks bats
- (ii) Equipments Tools being used in restoration works:- -
- (iii) Procedure take up in restoration works:- Departmental.
- (iv) Restored Length:- 125 m


21/12/2020
Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul