

GOVERNMENT OF BIHAR
FDR (2020-21)



बिहार सरकार

Name of Road- Dhaka Ghorasahan road Karsahiya chowk to Masaurha Bazar	Length-2.20 Km
Estimated Cost- Rs.:- 10,00,600.00	Block- Dhaka

Submitted By
Executive Engineer
R.W.D. (W) Division Dhaka

F.D.R (2020-21)

तकनीकी प्रतिवेदन

पथ का नाम :- दाका-करसहिमों रोड करसहिमों चौक से मसौदा बाजार

प्रखंड का नाम :- दाका

पथ की लम्बाई:- 2.20 कि.मी.

शीर्ष :- 3054.

प्राक्कलित राशि:- ₹. 10,00,000.00

अनुरक्षण अवधि :- निर्माणायी

दाका-करसहिमों रोड करसहिमों
प्रस्तुत प्राक्कलन चौक से मसौदा बाजार

में अतिवृष्टि/वाढ़ से क्षतिग्रस्त पथाशों में यातायात पुर्नस्थापन हेतु तैयार किया गया है जिसकी प्राक्कलित राशि मो. 10,00,000.00 रु० है। प्रस्तुत प्राक्कलन सचिव ग्रामीण कार्य विभाग बिहार पटना के पत्रांक:-2254, दिनांक:-30.06.2020 के निर्देशानुसार तैयार किया गया है। पथ में अतिवृष्टि/वाढ़ के कारण क्षतिग्रस्त पथाशों में Brick Bats से मरने का प्रावधान किया गया है, तथा आवश्यकता अनुसार पथ में हयूम पाईप का प्रावधान किया गया है।


प्राक्कलन में दिये गये दर वर्तमान अनुसूचित दर के अनुरूप है।


1.9.2020

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, दाका।


07/09/2020

सहाय अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, दाका


07/09/2020

कार्यपालक अभियंता

ग्रामीण कार्य विभाग


कार्य प्रमण्डल, दाका

Rate for Restoration work of Road from Dhaka Ghorasahan road Karsahiya
Bark to Masaurha Bazar for the year 2020-21 in Dhaka Block.

Lenth:- 2.20 Km

SL NO.	Name of Item	Unit	Quantity M ³	Rate Rs.	Amount Rs.
1	Labour for laying dry graded jhama khoa or stone filter under Bricks pitching in slope or apron including light ramming etc..... all complete as per approved design specification and direction of E/I. (Brick Bat) CH:- 35M to 45M, $10.00 \times 4.00 + 4.50/2 \times 0.300 + 0.600 + 0.300/3 = 17.00M^3$ CH:- 660M to 700M, $40.00 \times 4.00 + 6.00/2 \times 1.20 + 2.60 + 1.50/3 = 353.33M^3$ CH:- 2140M to 2200M, $60.00M \times 3.50 + 4.50/2 \times 0.300 + 0.75 + 0.300/3 = 108.00M^3$ 478.33M³ Less for H.P $2 \times 22/7 \div 4 \times (1.23)^2 \times 5.00$ (-) 11.88 M³ Total= 466.43M³	M ³	466.45	2053.84	958013.00
2	Supplying Fitting and and fixing Hume pipe 1000mm dia Hume pipe all complete as per approved design specification and direction of E/I. 2Row x 2 Nos. x 2.50M = 10M	M	10	4258.65	42587.00
			Total=	Rs.	10,00,600.00


1.9.2020
JE.


07/09/2020
AE.


07/09/2020
EE.

Cost Factor
T.A./T.C is accorded for Rs. 10,00,600 = 10
(..... crore..... Ten..... lacs..... thousand
..... Six..... hundred.....) only


SE. (R.W.D.)
works Circle
Motihari
27-12-20


Inspection Report for Flood Damage Works:-

Date:-

1. Name of PIUs:- Executive Engineer. R.W.D. (W) Div.ⁿ Dhaka
2. Name of Block:- Dhaka
3. Name of Road :- Dhaka Ghorasahan road Karsahiya Chowk to Masaurha Bazar.

(A) For Road

1. Damage Location Chainage:-
2. Damage Length:- 110 m
3. Name of Damage:- Road cutting due to Flood.
4. Details of Restoration Work:-
 - (i) Material being used in Restoration works:- Brick bats
 - (ii) Equipments Tools being used in restoration works:-
 - (iii) Procedure take up in restoration works:- Departmental.
 - (iv) Restored Length:- 110 m


26/12/2020
Executive Engineer
R.W.D. (W) Div.ⁿ
Raxaul