

| Name of Road:L030<br>to kataiya |                                                                                                                                                                                                                          | Block : benipatti |            | District: MADHUBANI   |           | Length :1.334 KM |       |         |        |
|---------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------|------------|-----------------------|-----------|------------------|-------|---------|--------|
| Item                            | Item of Work                                                                                                                                                                                                             | No s              | Length (M) | Width (M)             | Depth (M) | Quantit y        | Unit  | Rate    | Amount |
| 1.1                             | Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design,specification and direction of E/I (Brick Bats) |                   |            |                       |           |                  |       |         |        |
|                                 | Chainage                                                                                                                                                                                                                 |                   |            |                       |           |                  |       |         |        |
|                                 | 200 KM                                                                                                                                                                                                                   | 1                 | 15.50      | (3.30+4.00)/2<br>3.65 | 0.60      | 33.95            |       |         |        |
|                                 | 100 KM                                                                                                                                                                                                                   | 1                 | 20.00      | (3.30+2.50)/2<br>2.90 | 0.60      | 34.80            |       |         |        |
|                                 | 0.00 KM                                                                                                                                                                                                                  | 1                 | 75.00      | (4.50+3.50)/2<br>4.00 | 0.60      | 180.00           |       |         |        |
|                                 | 500KM                                                                                                                                                                                                                    | 2                 | 1.50       | 1.50                  | 0.60      | 2.70             |       |         |        |
|                                 |                                                                                                                                                                                                                          | 1                 | 1.00       | 1.50                  | 0.60      | 0.90             |       |         |        |
|                                 |                                                                                                                                                                                                                          |                   |            |                       |           | 252.35           | Cum   | 1867.76 | 471320 |
|                                 |                                                                                                                                                                                                                          |                   |            |                       |           | 231.69           | TOTAL |         | 471320 |

GST@12%  
LAB. CESS@1%  
SF  $(231.69 \text{ M}^3 \times 1063 \times 10\%) = 24629$   
TOTAL

57,929 - 56558  
4327 - 4713  
26824  
559416  
Total Rs 5,13,626 = 00

Say Rs 5,13,626 = 00

26.12.20

JE  
RWD  
BENIPAT

26/12/20

RWD BENIPATTI

27.1.21  
EE

RWD BENIPATTI

कार्यपालक अभियंता, आर का वि, कार्यक्षेत्र - बेंगलूर  
पाठ:- 01 कार्य दायित्व दिनांक:- 10/05/2021 के वरत खर्चा  
ऑफ प्रिविज के आधार पर  
जोस्ट-फैक्ट T/A 78 Rs 5,13,626 = 00  
(Rupees five lacs thirteen thousand six hundred twenty six only)

Superintending Engineer  
RWD, Works Circle, Darbhanga

13/05/2021