

Name of Road: Bhagwati asthan to loharpatti via champa mai asthan

Block : benipatti District: MADHUBANI Length :1.600 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)								
		Ch.(KM)								
		0.5 to 0.7			(0.90+1.80)/2	(0.45+0.90)/2				
			1	20.00	1.35	0.675	18.23		14.18	
					(0.95+1.9)/2	(0.40+0.80)/2				
			1	44.00	1.43	0.60	37.62			
					(0.70+1.40)/2	(0.35+0.70)/2				
			2	16.00	1.05	0.53	17.64			
		0.9 to 1.10			(0.90+1.80)/2	(0.30+0.60)/2				
			1	19.00	1.35	0.45	11.54			
					(0.50+1.00)/2	(0.40+0.80)/2				
			1	50.00	0.75	0.60	22.50		18.75	
					(0.60+1.20)/2	(0.40+0.80)/2				
			1	29.00	0.90	0.60	15.66			
					(0.90+1.80)/2	(0.60+1.20)/2				
			1	27.00	1.35	0.90	32.81			
					(0.55+1.10)/2	(0.55+1.10)/2				
			1	40.00	0.83	0.83	27.23		24.07	
					(0.75+1.50)/2	(0.45+0.90)/2				
			1	20.00	1.13	0.675	15.19			

