

# Estimate for Restoration work of Road from Bisfi To Singhiya for the year 2020-2021 in Bisfi Block

Length-7.703 KM

| Sr NO.            | Item of Work                                                                                                                                                                                                              |        |           |           |                       |                      |         |            |
|-------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|-----------|-----------|-----------------------|----------------------|---------|------------|
| 1                 | Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats) |        |           |           |                       |                      |         |            |
| Ch                | Nos                                                                                                                                                                                                                       | Length | Width     | Height    | Quantity              | Unit                 | Rate    | Amount     |
| 0.00 to 0.25 Km   | 1                                                                                                                                                                                                                         | 6.80   | 4.10 3.8  | 0.60      | 16.73                 | 15.50 M <sup>3</sup> |         |            |
|                   | 1                                                                                                                                                                                                                         | 28.00  | 4.00 3.75 | 0.60      | 67.20                 | 63 M <sup>3</sup>    |         |            |
|                   | 1                                                                                                                                                                                                                         | 19.00  | 3.75 3.70 | 0.60      | 42.75                 | 42.18 M <sup>3</sup> |         |            |
|                   | 1                                                                                                                                                                                                                         | 5.00   | 3.00      | 0.60      | 9.00                  |                      |         |            |
| 2.00 to 4.50 m km | 1                                                                                                                                                                                                                         | 37.00  | 4.00      | 2.00      | 296.00                |                      |         |            |
|                   | 1                                                                                                                                                                                                                         | 15.00  | 3.75 3.60 | 3.00 2.8  | 168.75                | 157.2 M <sup>3</sup> |         |            |
|                   | 1                                                                                                                                                                                                                         | 30.00  | 3.75 3.50 | 2.00 1.5  | 225.00                | 157.5 M <sup>3</sup> |         |            |
|                   | 1                                                                                                                                                                                                                         | 11.00  | 6.00 5.0  | 2.00 1.25 | 132.00                | 96.25 M <sup>3</sup> |         |            |
|                   |                                                                                                                                                                                                                           |        |           |           | 830.63 M <sup>3</sup> | 957.43 Cum           | 1867.76 | 1788245.72 |

Add 12% GST =Rs = 186170.00 214589.49  
 Add 1% L/Cess =Rs = 15514.00 17882.46  
 Total =RS 2020717.67  
 Say =Rs = 88295.00 2020718

Say Rs = 18,41,396 = 00

*[Signature]*  
 JE  
 RWD  
 Bisfi

*[Signature]*  
 AE  
 RWD  
 Bisfi

*[Signature]*  
 EE  
 RWD  
 Benipatti

कार्यपालक अभियंता का कार्य कि कार्य प्रमाणित देवीपुर का  
 02-05-2021 10.04.2021  
 पत्रिका :- 12/दिनांक :- 09.04.21 का द्वारा समीक्षा पांच  
 प्रतिलेख के आधार पर।

past fact to T/A 78, Rs 1841396 = 00

Supers Eighteen Lacs forty one thousand four hundred ninety  
 Six /only.

Superintending Engineer  
 RWD, Works Circle, Darbhanga

*[Signature]*  
 13/05/2021