

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM MURBALLA TO
FORBESGANJ PART-D

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- FORBESGANJ

ESTIMATED COST

1535714.00

कार्यपालक अभियंता का कार्यालय,
ग्रामीण कार्य विभाग कार्य प्रमंडल फारबिसगंज।
पत्रांक 811 फारबिसगंज/ दिनांक 02/05/2020

प्रेषण,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, फारबिसगंज।

सेवा में,

संबंधित सभी संवेदक
FMGSY/MMGSY/NABARD

विषय:-

प्रधोन्मंत्री ग्राम सड़क योजना अन्तर्गत निर्माणधीन पुलों के पास उचित संख्या में
हयूम पाइप डेकर डायवर्सन बनाने के संबंध में।

प्रसंग:-

जिला पदाधिकारी अररिया का स्तार्पांक 1841/सी0 एवं 1842/सी0 दिनांक-
02.05.2020

महाराष्ट्र

उपर्युक्त प्रसांगिक पत्र के आलोक में कहना है कि संभावित बाढ़ वर्ष 2020 की पूर्व
तैयारियों के मद्देनजर जिला पदाधिकारी अररिया के द्वारा निर्माणधीन सभी पुलों के पास
आवागमन बहाल रखने हेतु उचित संख्या के साथ मजबूत डायवर्सन उचित संख्या में
हयूम पाइप डेकर दिनांक 18.05.2020 तक पूर्ण करने का निर्देश प्राप्त हुआ है।

अतः आप सभी संबंधित संवेदकों को निर्देश दिया जाता है कि अपने
कनीय/सहायक अभियंता से सम्पर्क स्थापित करते हुए दिनांक 15.05.2020 तक
अपने-अपने पुलों के पास डायवर्सन बना कर इस कार्यालय को सूचित करें, तथा वर्ष
2020 में पुरी वर्षात पथों में सुगम आवागमन बहाल रखने एवं डायवर्सन में किसी प्रकार की
बूटी होने पर पुनः धीक करने की पूर्ण जबाबदेही आपकी होगी। डायवर्सन बनाते समय
भारत सरकार द्वारा जारी महामारी Covid-19 का निर्धारित Guide Line का पूर्ण
रूपेण अनुपालन करना सुनिश्चित करेंगे।

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।

स्तार्पांक 811 फारबिसगंज/ दिनांक 02/05/2020

प्रतिलिपि:- सभी कनीय अभियंता/सहायक अभियंता को निर्देश दिया जाता है कि अपने अपने क्षेत्राधीन
निर्माणधीन पुलों के पास संबंधित संवेदकों से सम्पर्क स्थापित कर उचित डायवर्सन बनवाना सुनिश्चित की
जाए।

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।

स्तार्पांक 811 फारबिसगंज/ दिनांक 02/05/2020

प्रतिलिपि:- अधीक्षण अभियंता ग्रामीण कार्य विभाग कार्य प्रमंडल, फारबिसगंज, मुख्य अभियंता-2 ग्रामीण कार्य
विभाग, पटना/ जिला पदाधिकारी अररिया / सचिव ग्रामीण कार्य विभाग, बिहार पटना को सूचना एवं
आव यक कार्रवाई हेतु समर्पित।

विरासतमाजन

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, फारबिसगंज।

Inspection Report for flood damage work

Date: 6/11/2020

1. Name of PIUs- Executive Engineer, RWD, Works Division - Farbagani

2. Name of Block/Road- Farbagani

A. For Road - Murhalla to Farbagani Part - 2

1. Damage Location/Chainage :

2. Damage Length : 152.0 m

3. Nature of Damage : Road width wash out

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: Local sand, boulder etc.
Roller, tractor, JCB etc.
Restore the damaged part of
Road to the above mentioned,
152.0 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM MURBALLA TO FORBESGANJ PART-11

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Divison, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	1100.75	627.77	691019.54
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	0.00	75.86	0.00
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	0.00	40.06	0.00
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	0.00	37.35	0.00
5	Construction of granular sub-base by providing well graded material, spreading in uniform layers with tractor mounted grader arrangement on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.				
		Cum	220.54	3084.04	680153.08

6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
	TOTAL AMOUNT =				1371173.00
	ADD 12.00 %GST=				164541.00
	SAY TOTAL AMOUNT =				1535714.00

[Signature]
6/11/2020
RWD WORKS
DIV.
FORBESGANJ

[Signature]
AE
RWD WORKS DIV. FORBESGANJ

E.E.
RWD WORKS
DIV. FORBESGANJ

Technically Approved for Rs 15,35,714.00 (Rupees
Fifteen lakh thirty five thousand seven hundred
and fourteen) only

[Signature]
S.E 30/11/20
RWD (W) circle
Krishnagar